

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-00720-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 36-5S-21W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: SPRATLAN/VEEH "A" Well #: 12
County: NORTON Total Vertical Depth: 3656 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 240 | 0 | 250 SX |
| PROD | 5.5 | 3651 | 0 | 200 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2010 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 300# hulls - 14 sxs gel spacer.
Squeezed at 2360'-2653'; 2164'-2197'; 1800'-1839' w/50 sxs; 2230' w/70 sxs.
Squeezed at 2164'-2653' w/150 sxs; 1800'-1839' w/20 sxs; 1120'-1157' w/20 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/28/2010 9:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pumped 14 sxs gel spacer - followed with 175 sxs 60/40 pozmix - 4% gel.
S.I.P. 200#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3647 | 3648 | | |
| 3641 | 3642 | | |
| 3581 | 3583 | | |
| 3557 | 3563 | | |
| 3533 | 3536 | | |
| 3458 | 3462 | | |
| 3396 | 3398 | | |

INVOICED
DATE 10-14-2010
INV. NO. 2011060022

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 02 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #41782.

Plugged through: CSG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

BLACK DIAMOND OIL
HAYS KS 67601-0641

#12 SPRATLAN - VEEH A OWWO

36-05S-21W
SW SW NE
KANSAS

City: NORTON Spot: C SW SW NE API 15-137-00720
Site: 4-1/4 S & 5-1/4 E OF DENSMORE KS Lat/Long: 39.57556 -99.63615
Field: RAY
FR: 06/30/2009 Spd: 07/09/2009 Drlg Cp: 08/20/2009 Issued: 03/08/2010 Revised: 03/08/2010

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Copyright 2010 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:

D&A, REAGAN, 11/2/2009

Contr: GASCHLER PULLING SVC

Geol: TONY RICHARDSON

Elev: 2228 KB, 2223 GL, 2226 DF

Formation Tops: (L-Log, S-Sample, D-Driller)

| | |
|-------------|------------|
| S TOP | 3192 -964 |
| S LANS | 3410 -1182 |
| S BKC | 3602 -1374 |
| S GORHAM SD | 3641 -1413 |
| S PBDT | 3650 -1422 |
| S REAGAN SD | 3652 -1424 |
| RTD OLD | 3656 -1428 |

Old Info:

Well Record: CITIES SERVICE OIL CO, #12
VEEH, SPD 05/20/1957, DC 05/30/1957, 8-5/8" 240
/ 220 SX (ALT 2), 5-1/2" 3651 / 200 SX, OIL, P 138
BO & 5.5 BWPD, REAGAN 3652-3656,
6/12/1957(CARD ISSUED 06/14/1957)

Contr: LOHMANN-JOHNSON

Finds:

COMMENT: WAS TEMP API IOG-60013
NO CORES OR DSTS

Comp Info: MICT - CO TO 3656, (REAGAN SD
OH), GSO, NAT, POP, IPP 138 BO & 5.5 BWPD,
6/7/1957

New Info:

Well Record: FR 06/30/2009, RE-ENTERED
07/09/2009, WSH DWN TO 3379, DC 08/20/2009,
PROD CSG ALREADY IN HOLE

Finds:

COMMENT: KCC API #15-137-00720-0001; ELEV
ON WO IS 2227 KB, 2222 GL; PROPOSED START
7/6/2009

Comp Info: TRGT ZN: REAGAN SD (OIL), PTD
3655 (REAGAN), SQZ'D HOLES IN CSG, SET
PLUG AT 2995, SQZ'D 2335-2360 W/150 SX CMT,
SET PKR AT 2067, SQZ'D 1800-1839 W/20 SX

BLACK DIAMOND OIL
HAYS KS 67601-0641

#12 SPRATLAN - VEEH A OWWO

36-05S-21W
SW SW NE
KANSAS
Side 2

Copyright 2010 Independent Oil & Gas Service, Inc. Wichita, KS

CMT, SQZ'D 1124-1157 W/20 SX CMT, RE-SQZ'D
2230 W/50 SX CMT & 2197 W/75 SX CMT, SQZ'D
2164-2197 W/250 SX, SPT 25 SX CMT AT 1969 &
25 SX CMT AT 157, DO CMT, SQZ 2300-2555
AFTER PMP 500 GAL AC (20% NE), SET PKR AT
2255 & SQZ'D W/50 SX CMT, PULL PKR TO 2099
& SQZ'D W/150 SX CMT, WSH DWN TO 3656,
RAN CORR LOG, MICT (6/24/2009) CO
(REAGAN SD OH), SWB & REC 18 BFPH (TR
OIL)/3 HRS, NON-COMMERCIAL PF (LKC)
3396-3398, 3533-3536, 3581-3583 W/4 SPF, AC
250 GAL (15% MCA) IN EA ZN 750 GAL AC
TOTAL, SION, SWB DWN & REC 3.0 BF (SO)/2
HRS, SION, TAGGED FISH AT 600' FROM SURF
WHEN ATTEMPTING TO PULL PLUG, REC FISH
SET PKR AT 3620, POP, P 10 BF (10% OIL)/24
HRS INTO SWB TANK, DECL TO 3 BF (TR
OIL)/24 HRS AFTER 10 DAYS OFF PMP, CO TO
BTM, (REAGAN SD OH), AC 750 GAL (15% INS),
NON-COMMERCIAL, SQZ'D OH W/15 SX CMT,
CO TO 3650, PF (GORHAM SD) 3641-3642,
3647-3648, W/4 SPF, AC 1500 GAL (15% INS),
SWB 12.76 BFPH (TR OIL), SION, PF (LKC)
3458-3462, 3557-3563, W/4 SPF, ISOLATED

LWR ZN & AC 500 GAL (15% MCA), SWB LD,
NSO, SION, FU 1600' FL (TR OIL ON TOP),
ISOLATED UPR PFS & SWB 7.2 BW/60", SI,
NON-COMMERCIAL, DECISION MADE TO P & A
11/2/2009