

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20770-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 26-8S-19W  
330 feet from N Section Line, 990 feet from W Section Line  
Lease Name: VEVERKA Well #: 6  
County: ROOKS Total Vertical Depth: 3413 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	170	0	130 SX
PROD	5.5	3704	0	525 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/24/2010 8:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 500# hulls - 16 sxs gel spacer.  
Squeezed from 1456' - 1518' w/150 sxs; 1331' w/350 sxs; 871' w/45 sxs.  
Perfs at 3085' - 3401'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/24/2010 9:30 AM KCC Agent: PAT BEDORE

**Actual Plugging Report:**

Hooked to 5 1/2" casing - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls - followed with 16 sxs gel spacer.  
Pumped 155 sxs 60/40 pozmix - 4% gel.  
S.I.P. 400#.  
Hooked to 8 5/8" x 5 1/2" annulus - pumped 20 sxs 60/40 pozmix - 4% gel.  
S.I.P. 200#.

**Perfs:**

Top	Bot	Thru	Comments
3190	3401		LANSING

INVOICED  
DATE 10-14-2010  
INV. NO. 2011060022

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 02 2010  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #41780.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

