

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-00237-00-01
Spot: NESENW Sec/Twnshp/Rge: 36-5S-21W
1650 feet from N Section Line, 2310 feet from W Section Line
Lease Name: WYRILL Well #: 5
County: NORTON Total Vertical Depth: 3637 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	240	0	200 SX CMT.
TI	2.375	3600		
PROD	5.5	3629	0	325 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2010 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 300# hulls - 13 sxs gel spacer. Perforated at 1435' and 1020'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/28/2010 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pumped 13 sxs gel spacer - followed with 175 sxs 60/40 pozmix - 4% gel with 100# hulls.
S.I.P. 250#.
Hooked to 8 5/8" x 5 1/2" annulus - pumped 5 sxs 60/40 pozmix - 4% gel.
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3575			
3561			
3540			
3507	3510		
3421	3425		
3372	3376		

INVOICED
DATE 10-14-2010
INV. NO. 2011060022

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 02 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #41783.

Plugged through: CSG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

JUN 30 2010

BLACK DIAMOND OIL
HAYS KS 67601


Replacement Card

36-05S-21W
120°W, C NE SE NW
KANSAS

#5 WYRILL OWWO

Cty: NORTON
Site: 4 S & 5-1/4 E OF DENSMORE KS
Field: RAY

Spot: W2 NE SE NW API 15-137-00237
Lat/Long: 39.57737 -99.63880



FR: 10/16/2006 Spd: 02/19/2007 Drig Cp: 02/20/2007 Issued: 06/18/2007 Revised: 09/03/2007

Copyright 2007 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:

OIL, P 5 BO & 40 BWPD, SHAW 3372-3376, LKC
3421-3575 OA, 4/1/2007

Revisions: CORR & INFO REL: 9/3/2007 - CORR WO;
WAS OIL WELL - TIGHT HOLE

Notes: CORR 3/17/1957 - ORIG FR IN APP NE SE NW
(CORR PER L & S)

Contr: GASCHLER PULLING SVC

Elev: 2205 KB

Formation Tops: (L-Log, S-Sample, D-Driller)

L	HEEB	3347 -1142
L	TOR	3374 -1169
L	LANS	3388 -1183
L	BKC	3582 -1377
L	GORHAM SD	3627 -1422
L	REAGAN SD	3628 -1423
	LTD OLD	3632 -1427
	RTD OLD	3633 -1428

Old Info:

Well Record: CITIES SERVICE OIL CO, #5
KITZKE, SPD 03/17/1957, DC 04/12/1957, 8-5/8"
240 / 400 SX (ALT 2), 5-1/2" 3629 / 325 SX, OIL, P
200 BOPD, NW, REAGAN 3631-3633,
5/1/1957(CARD ISSUED 05/03/1957)

Contr: LOHMANN-JOHNSON

Find:

COMMENT: WAS TEMP API IOG-60005;
REDESCRIBED LOC - IS ALSO 1650'FNL & 450'
FEL, NW/4; OPTIONAL LOG TOPS - LANS 3391
(-1186), BKC 3588 (-1383), REAGAN SD 3631
(-1426)
NO CORES
DST(1) 3375-3383 (TOR) 60-30-0-0, REC 20' M &
W, REMARK: FP NA ISIP 975#
DST(2) 3496-3543 (LKC) 60-30-0-0, REC 40' M,
REMARK: FP NA ISIP 500#

Replacement Card

BLACK DIAMOND OIL
HAYS KS 67601

36-05S-21W
120°W, C NE SE NW
KANSAS

#5 WYRILL OWWO

Copyright 2007 Independent Oil & Gas Service, Inc. Wichita, KS

Side 2

DST(3) 3525-3543 (LKC) 30-30-0-0, REC 20' M,
REMARK: PRESSURES NA
DST(4) 3629-3633 (REAGAN SD) 60-30-0-0, 350'
GIP, REC 75' HVLY GSY OCM, 165' MCO ISIP
960# IFP 75#-105#

Comp Info: MICT - CO TO 3633, (REAGAN SD
OH), FU 1670' OIL/24 HRS, NAT, POP, IPP 200
BOPD, NW, 5/1/1957 - (WELL P & A 4/3/1985)

New Info:

Well Record: FR 10/16/2006, RE-ENTERED
02/19/2007, WSH DWN, DC 02/20/2007, PROD
CSG ALREADY IN HOLE

Find:

COMMENT: KCC API 15-137-00237-0001; ELEV
ON WO IS 2198 GL; PROPOSED START
10/20/2006

Comp Info: TRGT ZN: REAGAN SD (OIL), PTD
3630 (REAGAN), MICT (3/12/2007) - CO, (REAGAN
SD OH), SWB DWN, NON-COMMERCIAL, SET
CIBP AT 3610, PF (LKC) 1/3575, 1/3561, 1/3540,
AC 3000 GAL (28% NE), SWB LD, SO, PF (LKC)
3507-3510, W / 4 SPF, AC 750 GAL (28% NE) &
250 GAL (15% MCA), SWB LD, SO, PF (LKC)
3421-3425, W / 4 SPF, AC 750 GAL (28% NE) &

250 GAL (15% MCA), SWB LD, SO, PF (TOR)
3372-3376, W / 4 SPF, AC 750 GAL (28% NE) &
250 GAL (15% MCA), SWB LD, SO, SET 2-3/8"
TBG AT 3600, NO PKR, POP, IPP 5 BO & 40
BWPD (GR 32), DOFP 4/1/2007, COMMINGLED