

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23012-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 6-7S-20W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: LOEFFLER B Well #: 4
County: ROOKS Total Vertical Depth: 3715 feet

Operator License No.: 33306
Op Name: BLAKE EXPLORATION, LLC
Address: 201 S MAIN PO BOX 150
BOGUE, KS 67625

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	213	0	150 SX
PROD	4.5	3714	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2010 9:00 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: MIKE DAVIGNON Company: BLAKE EXPLORATION, LLC Phone: (785) 216-0062

Proposed Plugging Method: Tubing was parted - tried overshot and wash pipe - got out some pieces of tubing - then tried bit - no progress. PC at 1805' w/400 sxs. Squeezed 1300' and 2100'.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 06/30/2010 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1865' - pumped 100 sxs 60/40 pozmix - 4% gel.
Pulled to 925' - circulated with 125 sxs cement.
POOH. Topped off with 15 sxs cement.
Max. P.S.I. 400#.

Perfs:

Top	Bot	Thru	Comments
3610	3612		
3590	3595		
3486	3488		
3466	3470		
3430	3434		

INVOICE
DATE 10-14-2010
INV. NO. 2011060023

RECEIVED
JUL 08 2010
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

JUL 07 2010

N-B COMPANY, INC
 RUSSELL, KS 67665-0506

6-07 -20W
 SW NW SE

#1 LOEFFLER "C"

site: 1-1/4 N & 16-1/2 W OF STOCKTON, KS city: ROOKS API 15-163-23012
 contr: EMPHASIS OIL OPERATIONS field: LESAGE NW EXT (1/8 E)
 geol: BILL GOFF

fr date 08/03/88 spd date 08/06/88 drig comp 08/13/88 card issued 11/02/88 last revised 11/02/88

ELV: 2206 KB LOG	
tops.....	depth/datum
*DAK SD.....	850 +1356
*B/DAK SD.....	1040 +1166
*CED HILL.....	1295 +911
*B/CED HILL.....	1520 +686
TOP.....	3189 -983
HEEB.....	3387 -1181
TOR.....	3410 -1204
LANS.....	3426 -1220
BKC.....	3621 -1415
CONG.....	3657 -1451
ARB.....	3699 -1493
RTD.....	3715 -1509

IP status:

OIL, P 33-BO & 150 BWPD, LKC 3430-3612 OA,
 *DRILLER TOP
 NOTE: CORRECTION: 8/10/88 - ORIGINALLY FIRST
 REPORTED AS #5 LOEFFLER "B"; 8/31/88 - FIRST
 CORRECTION CHANGED TO #4 LOEFFLER "B"
 CSG: 8-5/8" 201 / 150 SX, 4-1/2" 3714 / 150 SX
 NO CORES
 DST (1) 3386-3440 (TOR, LANS), / 30-60-60-90, REC 40'
 GSY OIL, 120' OCM, 115' SW ISIP 628# FSIP 618#
 IFP 78# -107# FFP 126# -174#
 DST (2) 3455-3485 (LKC), / 30-60-30-60, 510' GIP, REC
 185' CLEAN GSY OIL, 180' MCO ISIP 560# FSIP 560#
 IFP 68# -97# FFP 126# -145# ..

COPYRIGHT 1988
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

(over)