

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20829-00-01
Spot: SWSENE Sec/Twnshp/Rge: 30-33S-28W
3013 feet from S Section Line, 1110 feet from E Section Line
Lease Name: MOHLER UNIT Well #: 7
County: MEADE Total Vertical Depth: 5770 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5690		
SURF	8.625	1548		WITH 700 SX CMT
COND	20	65		
PROD	4.5	5770	2223	WITH 150 SX CMT

Well Type: EOR UIC Docket No: E26993.1 Date/Time to Plug: 06/28/2010 5:30 PM
Plug Co. License No.: 7840 Plug Co. Name: BORDERLINE, INC.
Proposal Rcvd. from: DAVE PAULEY Company: C.H. TODD Phone: (316) 264-7566

Proposed
Plugging
Method:

PUMP 50# HULLS @ 4950'. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: PARTIAL
Date/Time Plugging Completed: 06/29/2010 6:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG PUMP 50 SX CMT TO 4950' THRU 2 3/8" TBG. WAIT ON CMT 12 HOURS.
TAG @ 4375'. 2ND PLUG RIHWT TO 1560'. PUMP 20 SX GEL & 50 SX CMT. 3RD
PLUG PULL TBG TO 600' & PUMP 50 SX CMT. 4TH PLUG PULL TBG TO 60' & PUMP
20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5701	5706		
5638	5654		SQUEEZED W/75 S
5602	5622		

INVOICED
DATE 10-14-2010
INV. NO. 2011060027

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 06 2010


CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

RECEIVED

JUN 30 2010

KCC DODGE CITY