

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-19001-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 13-31S-18W
2143 feet from S Section Line, 5133 feet from E Section Line
Lease Name: PYLE A Well #: 2
County: COMANCHE Total Vertical Depth: 1008 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		660		WITH 2 SX CMT
SURF	8.625	505		WITH 200 SX CMT
PROD	5.5	1008	0	WITH 200 SX CMT

Well Type: SWD UIC Docket No: D16057.0 Date/Time to Plug: 06/28/2010 2:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/28/2010 3:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 660' WITH 2 SX CMT. RUN TBG TO 620' & PUMP 69 SX CMT. CMT TO SURFACE. PULL TBG & TOP OFF WITH 6 SX CMT. PUMP DOWN BACKSIDE WITH 5 SX CMT TO 300#. HELD AT 300#.

Perfs:

Top	Bot	Thru	Comments
710	746		CEDAR HILLS

INVOICED
DATE 10-14-2010
INV. NO. 2011060029

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Jerry W. Stapleton
(TECHNICIAN)
PRT/IT

RECEIVED
JUN 29 2010
KCC DODGE CITY

RECEIVED
JUL 01 2010
KCC WICHITA