

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-22053-00-00
Spot: SWNWSESE Sec/Twnshp/Rge: 18-30S-13E
710 feet from S Section Line, 1000 feet from E Section Line
Lease Name: BARNABY-GLORY Well #: 1
County: ELK Total Vertical Depth: 1594 feet

Operator License No.: 7786
Op Name: CODY, KEN L.
Address: 1125 RD 27
LONGTON, KS 67352

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40		10 SX
PROD	4.5	1591		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/23/2010 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: KEN L. CODY Company: _____ Phone: (620) 642-6123

Proposed Plugging Method: PUMP CEMENT THROUGH A 2" PIPE; A 50' CEMENT PLUG FROM TD TO 1541'; GEL TO 750'; CEMENT PLUG FROM 750' TO 700'; GEL TO 350'; CEMENT FROM 350' TO SURFACE.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 06/23/2010 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 1500' gelled hole and spotted 10 sack plug. Pulled tubing and perforated at 850' and 350'. Ran 2" back to 850' and spotted 10 sack plug. Pulled tubing up to 350' and circulated cement to surface. Pulled 2" and topped well off. A total of 55 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1580	1582		
1570	1574		

RECEIVED
JUL 8 2010
DAS
KCC Chanute Dist. #3


INVOICED
DATE 10-14-2010
INV. NO. 2011060030

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED

JUL 12 2010

KCC WICHITA