

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00734-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 2-11S-21W
5353 feet from S Section Line, 5011 feet from E Section Line
Lease Name: COOK Well #: 10
County: TREGO Total Vertical Depth: 3653 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3644		
SURF	8.625	160	0	UNKNOWN
PROD	5.5	3648	0	UNKNOWN

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2010 11:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (620) 793-9090

Proposed Plugging Method: Ordered 535 sxs 60/40 pozmix - 4% gel - 700# hulls.
CIBP at 3644'. Holes in casing at 2850'-2700'; 1860'-1890'.
According to operator - well was two staged and squeezed.
Operator elected all cement plug.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2010 9:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

07/20/2010 - Professional Pulling Service RIH with tubing to 3500'.
Quality rigged to tubing and pumped 150 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in.
Pulled tubing to 2400'. Quality rigged to tubing and pumped 100 sxs cement with 200# hulls mixed in - no circulation.
Pulled tubing to 1500'. Quality rigged to tubing and pumped 160 sxs cement with 200# hulls - no circulation.
Pulled tubing to 800'. Quality rigged to tubing and pumped 70 sxs cement - no circulation.
Left set over night.
07/21/2010 - RIH to 600' - pumped 50 sxs cement to circulate cement up 5 1/2" casing.
Rigged to 8 5/8" casing and pumped 5 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.
Pulled tubing and topped off - hole standing full.

Perfs:

Top	Bot	Thru	Comments
3629	3637		
3536	3540		
3520	3524		
3500	3506		
3438	3442		
3426	3432		
3381	3387		

INVOICED
DATE 10-15-2010
INV. NO. 2011060028

RECEIVED
JUL 26 2010

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4124.

KCC WICHITA

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN)

CM

PEEL-HARDMAN OIL

#10 COOK

2-11-21W
NW NW NW

Contr. PEEL BROS

TREGO

County

E 2078

Comm.

Comp.

11-16-56

IP

265 BOPD/ARB

Tops	Depth	Datum
HEEB	3300	-1222
LANS	3340	-1262
ARB	3630	-1552
TD	3653	-1575

Casing
5" 3648

DP: CO 3653: ACID 500: 10 BO
PH/8 HRS

WHITE SW POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS