

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-19046-0001

API NUMBER completed on 10/49

LEASE NAME Hall A

WELL NUMBER 1D

2970 Ft. from S Section Line

1700 Ft. from E Section Line

SEC. 14 TWP. 11 RGE. 17 ~~X~~ (W)

COUNTY Ellis

Date Well Completed 10/49

Plugging Commenced 1/20/87

Plugging Completed 1/27/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cities Service Oil and Gas Corporation

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112

PHONE#(405) 949-4432 OPERATORS LICENSE NO. 5447

Character of Well oil SWD ANB KCC

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? completed on 10/49 if not, is well log attached? yes

Disposal ~~Producing~~ Formation Arbuckle Depth to Top OH 3419 Bottom 3930' T.D. 3930'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	(Disposal only)	3419	3930	8-5/8"	767'	
				5-1/2"	3419	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Tied on to 8-5/8" csg and pumped 6 sx 65/35 Poz. + 10% gel and 2% Econolite. Tied on to 5-1/2" csg and pumped 484 sx 65/35 Poz + 10% gel and 2% Econolite and 1200# hulls. State witness: Mr. Dennis Hamel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services Company License No. _____

Address Hays, Kansas 67601

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del G. Oliver, Engineering Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Del G. Oliver
3545 NW 58th Street

(Address) Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 4th day of February, 19 87

Jessie Jo Howeth
Notary Public for Oklahoma Commission

My Commission Expires: 4-24-89

RWD FEB 9 1987 Form CP-4
02-09-87 CONSERVATION DIVISION
Wichita, Kansas Revised 08-84

