

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas


WELL PLUGGING RECORD

15-051-02161-0001

Ellis County, Sec. 14 Twp. 11 Rge. (E) 17 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Center of SE SW SW
Lease Owner Cities Service Oil
Lease Name Hall "A" Well No. 2
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 1/21/38 19
Application for plugging filed 5/1/52 19
Application for plugging approved 5/2/52 19
Plugging commenced 5/13/52 19
Plugging completed 5/14/52 19
Reason for abandonment of well or producing formation Non-Commercial

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 3/17/52 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Arbuckle Depth to top 3380' Bottom Total Depth of Well 3450' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				15-1/2	131'	0
				10-3/4	1102'	0
				7	3381	2642'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug with mud to 360', 10' rock, 20 sacks cement 350' to 310', mud to 25', 10' sx. to surface.

RECEIVED
STATE CORPORATION COMMISSION

MAY 23 1952 05-23-52

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. W. Patterson
Address Box 12, Arkansas City, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
James Porter (employee of owner) or (owner/operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Porter

Box 553, Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 27th day of May, 1952

W. G. Smith Notary Public

PLUGGING
FILE SEC 14 T 11 R 10
BOOK PAGE 13 LINE 18

WELL RECORD

15-051-02161-0001

Company Cities Service Oil Co. Well No. 2 Farm Hall "A"
 Location 330' North and 978.5' East of SW Corner Sec. 14 T. 11 R. 17W
 Elevation 1678' County Ellis State Kansas
 Deepening February 1, 1950 Contractor Folger Drilling Company
 Drig. Comm. February 5, 1950 Acid None
 Deepening February 5, 1950
 Drig. Comp. February 5, 1950
 T. D. 3450' Initial Prod. Pumped 11 oil, 540 water, 24 hrs. (3-20-50)
 P.B.T.D. 3406'

DEEPENING RECORD

CASING RECORD:

15-1/2" @ 131' cen. 100 sx cement
 10-3/4" @ 1102' cen. 400 sx cement
 7" @ 3381' cen. 275 sx cement

101' of 5-1/2" liner at 3450' with 50 sacks cement.

FORMATION RECORD:

Old Total Depth	3388
line	3388-3392
line & green shale	3401
line	3411
line & green shale	3415
line	3423
line & chert	3429
line	3436
line & green shale	3442
line	3445
line, sandy	3450 T. D.

Corr. Top Arluckle 3380'
 Penetration 70'
 Total Depth 3450'

Drilled cement to 3443 SIM.

Perf. 36 shots 3417-23.

2-11-50 Acidized 500 gals. 3417-23.
 Pumped 90-99% water.

Set retainer at 3330 and squeezed w/ 50 sacks cement; 25 sacks through perforations at 1800%.

Drilled cement to 3431 SIM.

Perf. 30 shots 3417-22.

2-23-50 Acidized 500 gals. 3417-22.
 Pumped 98% water; did not recover all oil used in acidizing.

Set Lane-Wellsplug at 3411; dumped 1/2 sack cement on plug; P.B.T.D. 3406 SIM.

Perf. 32 shots 3399-3405.
 500' fluid in 10 mins.
 1200' fluid in 40 mins.
 1700' fluid in 1 hr. 5 mins.
 1915' fluid (220' oil and 1695' water) in 2 hrs. 5 mins.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY - 2 1952
 CONSERVATION DIVISION
 Topeka, Kansas

PLUGGING
 FILE NO. 983-T-CR
 BOOK PAGE LINE