

API NUMBER 15-051-21743-  
 LEASE NAME Hall 'A'  
 WELL NUMBER #7  
1090 Ft. from S Section Line  
4950 Ft. from E Section Line  
 SEC. 14 TWP. 11 RGE. 17 (E) or (W)  
 COUNTY Ellis  
 Date Well Completed 9-26-79  
 Plugging Commenced 1-29-86  
 Plugging Completed 1-29-86

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Zinszer Oil Company  
 ADDRESS 206 W. 26th, Hays, KS 67601  
 PHONE#(913) 625-6246 OPERATORS LICENSE NO. 6239  
 Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #6, Hays

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3385' Bottom Reached T.D. 3387.5'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Arbuckle</u>	<u>Oil</u>	<u>Surface</u>	<u>211'</u>	<u>8 5/8"</u>	<u>211'</u>	<u>None</u>
		<u>Surface</u>	<u>3386'</u>	<u>5 1/2"</u>	<u>3386'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Circulated 150 sx cement into annulus, mixed 200 sx cement into 5 1/2" casing with 3 sx hulls. Maximum pressure 1200 PSI, shut-in pressure 800 PSI. Cement was 60/40 with 3% CC and 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address P.O. Box 31, Russell, Kansas, 67665

STATE OF Kansas COUNTY OF Ellis, ss.

Perry S. Henman

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Perry S. Henman

(Address) RR2 Box 11, Ellis, KS 67637

SUBSCRIBED AND SWORN TO before me this 31<sup>st</sup> day of January, 1986

Robert G. Schibi  
 Notary Public

My Commission Expires: July 31, 1986

**ROBERT J. SCHIBI**  
 STATE NOTARY PUBLIC  
 Ellis County, Kansas  
 My Appt. Exp. July 31, 1986

RECEIVED  
 STATE CORPORATION COMMISSION  
02-03-86  
 FEB 3 1986

# DREILING OIL, INC

Victoria, Kansas 67671

15-051-21743-0000

## WELL LOG

Richard Zinszer  
 206 W. 26th  
 Company Hays, KS 67601  
 Farm Hall A No. 7  
 Total Depth 3387'  
 Comm. 8-17-79 Comp. 8-24-79  
 Contractor Dreiling Oil, Inc.  
 Rt. #1  
 Victoria, KS 67671

Sec. 14 Twp. 11 Rng. 17W  
 Location NW SW SW  
 County Ellis  
 Elevation: 1854' K. B.  
 1851' D. F.  
 1849' G. R.

Casing Record  
 211' - 8 5/8"  
 3386' - 5 1/2"

Cement Record  
 140 sacks cement  
 125 sacks cement


Production:

### Figures Indicate Bottom of Formations


0'	120'	Shale
120'	216'	Shale
216'	630'	Shale
630'	740'	Sand
740'	916'	Shale
916'	1073'	Shale
1073'	1119'	Anhydrite
1119'	1275'	Shale
1275'	1678'	Shale
1678'	1916'	Shale & Lime
1916'	2125'	Lime & Shale
2125'	2308'	Lime
2308'	2499'	Shale & Lime
2499'	2769'	Lime & Shale
2769'	2845'	Lime
2845'	2937'	Lime
2937'	3034'	Lime
3034'	3120'	Lime
3120'	3210'	Lime
3210'	3292'	Lime
3292'	3364'	Lime
3364'	3386'	Lime
3386'	3387'	Lime
3387'	T.D.	

STATE OF KANSAS)  
 )ss  
 COUNTY OF ELLIS)

I, Joseph A. Hess, Secretary - Treasurer of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Hall A #7.

  
 Joseph A. Hess

Subscribed and sworn to before me this 28th day of August, 1979.

  
 Patty Dreiling Notary Public

My appointment expires: August 30, 1982.



RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 27 1986  
 CONSERVATION DIVISION  
 WICHITA, KANSAS