

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-02171-00-00
11-16-1939

15-051-02171-000

LEASE NAME Mai

TYPE OR PRINT

WELL NUMBER 7

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1650 Ft. from S/N Line of Section (circle one)

330 Ft. from E/W Line of Section (circle one)

LEASE OPERATOR Cattlemans Oil Operations

SPOT LOCATION SE - NE - SE -

ADDRESS 2260 Catherine Rd.

SEC. 14 TWP. 11 S. RGE 17 W (E) or (W)

CITY, STATE, ZIP Hays, Kansas 67601

COUNTY Ellis

PHONE# 785 625-5394 OPERATORS LICENSE NO. 7064

Date Well Completed 11-16-1939

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 12-31-99

Date Plugging Completed 12-31-99

The plugging proposal was approved on 12-15-99 (date)

by Roger Moses (KCC District Agent's Name)

Is ACO-1 filed? ? If not, is well log attached? none on record (yes)

Producing Formation(s) Lansing KC Depth to Top 3046 Bottom 3300 T.D. 3357

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Lansing KC	oil & water	3046	3300	13"	129'	none
Arbuckle	oil & water	3359	3361	5 1/2"	3359	none

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Ran 2" tubing to 1450', mixed 200 sks cement with 500# hulls, pumped down tubing, pulled 600' & circulated cement, pulled balance of tubing & filled hole with cement 30 sks, 60/40; topped casing with 5 sks. Pressured backside 500#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing & company tools

License No. 7064

Address P O Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Cattlemans Oil Operations

STATE OF Kansas COUNTY OF Ellis, ss.

Leo Dorzweiler (Employee of Operator or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Leo Dorzweiler

(Address) 2260 Catherine Rd. Hays, Kansas 67601

SUBSCRIBED AND SWORN TO before me this 1st day of January, 19 2000

Viola Dorzweiler
Notary Public

My Commission Expires: 4-20-2003



RECEIVED
STATE CORPORATION COMMISSION

Form CP-4
Revised

JAN 28 2000

CONSERVATION DIVISION

(R)