

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15,051-22,014-00-00

LEASE NAME Mai

WELL NUMBER #11

990 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 14 TWP. 11 RGE. 17 (E) or (W)

COUNTY Ellis

Date Well Completed _____

Plugging Commenced 3-18-88

Plugging Completed 4-28-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cattleman's Oil Operations

ADDRESS HC 399 Box 74, Hays, Ks 67601 Was RR. Price

PHONE # 913-625-5394 OPERATORS LICENSE NO. 7064

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Four (4)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3359'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	241'	None
				5-1/2"	3358'	308.96'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 2950' and 5 sacks cement. Shot casing at 2500' 1800', 1500', 1200', 1000', 600', 400' and 300'. Pulled 7 joints of 5-1/2" casing. Allied squeezed well with 600# hulls and 200 sacks ATL cement.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Kansas 67530

RECEIVED SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 88
STATE CORPORATION COMMISSION

Commission Expires: MAY 04 1988

05-04-88
CONSERVATION DIVISION
Wichita, Kansas

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-91

Iona M. Leatherman
Notary Public