


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 15 Twp. 11 Rge. 17 (X) (W)
Location as "NE/CNWxSWx" or footage from lines. SE SE SW
Lease Owner Sohio Petroleum Company
Lease Name Bemis "B" Well No. 7
Office Address Box 673, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed August, 1937
Application for plugging filed November 2, 1955
Application for plugging approved November 3, 1955
Plugging commenced November 16, 1955
Plugging completed November 20, 1955
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production July, 1954
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3417' Bottom 3421' Total Depth of Well 3421.5' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		--	1128	10"	1128	Pulled
		--	3417	7"	3417	1411'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with rock 3421-3400'. Dumped
4 sacks cement - top 3385'. Filled hole
with mud to 300'. Rock bridge 300-285'.
Dumped 25 sacks to 240'. Filled with mud
to 36'. Rock bridge 36-26'. Ten sacks
to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Company
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
J. H. Bond (employee of owner) ~~EXCISE OF PROPERTY~~ of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond.
(Address) _____

SUBSCRIBED AND SWORN to before me this 22nd day of November, 19 55

January 24, 1959

My commission expires _____

Deneck B. Brown Notary Public.

RECEIVED
NOV 23 1955
11-23-55
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 15 T 11 R 12 W
BOOK PAGE 13 LINE 27

WELL LOG

LOG OF MARGAY OIL CORPORATION BEMIS B-7
Section 22-11S-17W, Ellis County, Kansas

Commenced: 7-3-37

Completed: 8-2-37

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>
0	35	Surface	1935	1952	Shale & shells
Set & cemented	15½" casing	34'10"	1952	2089	Lime
35	104	Shale	2089	2097	Shale
104	605	Shale & shells	2097	2364	Lime
605	614	Shale	2364	2375	Sticky blue shale
614	625	Pyrites	2375	2460	Lime
625	670	Shale & shells	2460	2476	Red Rock
670	783	Sand	2476	2521	Shale & shells
783	864	Shale & shells, red rock	2521	2571	Shale
864	1027	Shale & shells	2571	2686	Shale & shells
1027	1110	Sticky shale	2686	2780	Shale
1110	1112	Chalk	2780	2867	Shale & lime
1112	1117	Anhydrite	2867	2920	Lime
1117	1128	Anhydrite	2920	2930	Red bed
Set & cemented	1128' of 10" casing		2930	3151	Lime
with 300 sacks cement			3151	3147	S. L. M. Correction
1128	1160	Anhydrite	3147	3172	Shale & lime
1160	1267	Shale & red rock	3172	3360	Lime
1267	1330	Lime	3360	3370	Shale
1330	1412	Shale & red rock	3370	3394	Lime
1412	1490	Shale	3394	3406	Shale
1490	1640	Salt & shale	3406	3413	Sand
1640	1660	Lime	3413	3418	Lime
1660	1718	Sticky shale	3418	3417	S. L. M. Correction
1718	1828	Lime	Set & cemented 7" O. D. casing		
1828	1902	Lime, broken	with 150 sacks cement		
1902	1935	Red rock	3417	3421½	Lime, oil in hole

PLUGGING

FILE SEC 15 T 11 R 124

BOOK PAGE 13 LINE 27

NOV 10 1937
CONSERVATION DIVISION
Wichita, Kansas