

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-051-21875-0000

LEASE NAME Bemis B

WELL NUMBER 9

2310 Ft. from S Section Line

3750 Ft. from E Section Line

SEC. 15 TWP. 11 RGE. 17 (X) or (W)

COUNTY Ellis

Date Well Completed 2/28/80

Plugging Commenced 12/11/96

Plugging Completed 12/11/96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Zinszer Oil Company, Inc.

ADDRESS P.O. Box 211, Hays, KS 67601

PHONE#(913) 625-9448 OPERATORS LICENSE NO. 6239

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/5/96 (date)

by Herb Daines (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3383 Bottom 3388 T.D. 3388

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil & Water	240	0	8 5/8	240	none
		3383	0	5 1/2	3383	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Perforated 4 holes at 1625' and at 1075'.

Squeezed down 5 1/2" casing 250sx 60/40 poz 10% gel with 500# hulls, 800# max.,

100# shut in pressure. Squeezed down 8 5/8" casing 40sx 60/40 poz 10% gel,

500# max., 200# shut in pressure.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zinszer Oil Company

STATE OF Kansas COUNTY OF Ellis, ss.

Perry S. Henman

(Employee of Operator) ~~XXXXXXXXXX~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 211, Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 20th day of February, 19 97

[Signature]
 Notary Public

My Commission Expires: August 24, 1998



RCWD
 02-24-97

DREILING OIL, INC.

Victoria, Kansas 67671

15-051-21875-0000

WELL LOG

Company	Richard Zinszer 206 W. 26 Hays, KS 67601	Sec.	15	Twp.	11	Ang.	17
Farm	Bemis	No.	B-9	Location	120' N Of NW NE SW		
Total Depth	3,384'	County	Ellis				
Comm.	1-3-80	Comp.	1-9-80	Elevation:	1848	K. B.	
Contractor	Dreiling Oil, Inc. Rt. #1 Victoria, KS 67671				1845	D. F.	
					1843	G. R.	

Casing Record
240' - 8 5/8"
3,383' - 5 1/2"

Cement Record
160 sacks cement
cemented w/150 sacks
common

Production:


Figures Indicate Bottom of Formations

0'	40'	Top Soil-Clay
40'	60'	Post Rock
60'	545'	Sand & Shale
545'	580'	Shale
580'	715'	Sand
715'	1052'	Shale & Red Bed
1052'	1097'	Anhydrite
1097'	1990'	Shale
1990'	2200'	Shale & Lime
2200'	2825'	Lime & Shale
2825'	3384'	Lime
3384'	T.D.	


RECEIVED
KANSAS CORP COMM
JAN 24 P 3:00

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Joseph A. Hess, Secretary Treasurer of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Bemis B-9.


JOSEPH A. HESS

Subscribed and sworn to before me this 15th day of January, 1980.


Cecilia Basgall Notary Public

CECILIA BASGALL
NOTARY PUBLIC
Ellis County, Kansas

My appointment expires: November 17, 1980.