

15-051-21367-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Ellis SEC. 15 TWP. 11 RGE. 17 ~~NE~~W
 Location as in quarters or footage from lines:
130' S 440' W of C W/2/ W/2 SE/4

Lease Owner Richard H. Zinszer
 Lease Name Simpson Well No. #1
 Office Address 206 W. 26th - Hays, Kansas 67601
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced April 24, 1982
 Plugging completed April 26, 1982
 Reason for abandonment of well or producing formation
Depleted

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation _____ Depth to top _____ bottom T.D. 3464'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	243'	NONE
				5 1/2"	3463'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Squeezed well with two (2) sacks hulls and one hundred seventy-five (175) sacks 50/50 pozmix cement with 4% added gel and 3% calcium chloride down the 5 1/2" casing. Squeezed the annulus between the 5 1/2" and 8 5/8" with one (1) sack hulls and seventy-five (75) sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION

05-18-82 MAY 18 1982

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Rockhold Engineering, Inc. CONSERVATION DIVISION
 Wichita Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

James W. Rockhold
 James W. Rockhold - Box 698 - Great Bend
 (Address) Ks. 67530

SUBSCRIBED AND SWORN TO before me this 4th day of May, 19 82

My Commission expires: _____



Ruth Brack
 Notary Public.

15-051-21367-0000

BERGMAN DRILLING, INC.

DRILLERS LOG

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1987

Re: Simpson # 1
SE/4 Section 15-11S-17W
Ellis County, Kansas

OPERATOR: Richard H. Zinser

CONTRACTOR: Bergman Drilling, Inc.

COMMENCED: October 2, 1977


COMPLETED: October 9, 1977

TOTAL DEPTH 3464' Ran 236' of 8 5/8" w/175 sacks

0	250	Rock Post - Shale - Sand	
250	605		
605	1110	Shale- Shells - Red Bed	
1110	1139	Anhydrite	
1139	1290	Red Bed - Shale	
1290	1730	Red Bed - Shale	
1730	1915	Shale - Lime	
1915	2125	Shale - Lime - Broken Lime	
2125	2295	Lime - Shale	
2295	2515	Shale - Lime	
2515	2885	Shale - Lime	
2885	2935	Lime - Shale	
2935	3110	Lime - Shale	
3110	3335	Lime	
3335	3420	Lime - Shale	
3420	3464	Arbuckle	
3464		Total Depth	Set 5 1/2 @3463 W/125 sacks 20 gal latex.

We certify that the above and foregoing to be true and correct copy of the drillers log on the # 1 Simpson, located in Ellis County, Kansas as revealed by the records of Bergman Drilling, Inc.


Harold I. Bergman, Manager


Alma A. Neises, Notary Public

Subscribed and sworn to before me this 11,th day of October, 1977
My commission expires May 31, 1978.