

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-23,042 0000

LEASE NAME Simpson

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #3

1730 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 15 TWP. 11 RGE. 17 (K) or (W)

COUNTY Ellis

LEASE OPERATOR Zinszer Oil Company

ADDRESS 206 W. 26th, Hays, Kansas 67601

PHONE# (913) 625-9448 OPERATORS LICENSE NO. 6239

Date Well Completed 8/28/82

or 726-3768

Character of Well Oil

Plugging Commenced 2/11/92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/11/92

The plugging proposal was approved on 2/5/92 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Simpson Depth to Top 3429 Bottom 3431 T.D. 3520

Show depth and thickness of all water, oil and gas formations. CIBP at 3415

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC 3137-3372	water	259	2	8 5/8	257	none
Simpson 3429-31	oil & water	3516	0	5 1/2	3516	none
Arbuckle 3436-56	water					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perforate Anhydrite @ 1125', perforate base of Dakota Fm @ 573', spot 100sx 60/40 8% gel thru tubing at 3340', spot 130sx 60/40 8% gel thru tubing at 1800' and circulated to surface, pulled tubing, pumped 50sx 60/40 8% gel down 5 1/2" casing max. pressure 100#, pumped down 8 5/8" casing 95sx 60/40 8% gel max. pressure 200#, shut in pressure 100#.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. _____

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zinszer Oil Company


STATE OF Kansas COUNTY OF Ellis, ss.

Perry S. Henman (Employee of Operator) ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 206 W. 26th, Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 13th day of March, 19 92



Commission Expires: February 8, 1996

Cynthia A. Weigel
Notary Public
Cynthia A. Weigel

K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY

Rotary Drilling Contractors

1008 DOUGLAS BUILDING
104 S. BROADWAY
WICHITA, KANSAS 67202

15-051-23042-
0000

June 25, 1982

Company:	Zinszer Oil Company
Farm:	#3 Simpson
Location:	SW NW SE
Section:	15-11S-17W
County:	Ellis
Contractor:	Woodman & Iannitti Drilling Company
Comm:	June 17, 1982
Comp:	June 24, 1982
Total Depth:	3520'
Casing:	6 joints 8-5/8" set w/165 sx.

Figures Indicate Bottom Formations:

259	Shale
535	Shale
650	Sand & Shale
785	Sand
1114	Red Bed
1137	Anhydrite
1149	Anhydrite
1595	Shale
1855	Shale
2117	Shale & Lime
2360	Shale & Lime
2570	Shale & Lime
2787	Shale & Lime
2930	Shale & Lime
3040	Lime & Shale
3140	Lime & Shale
3235	K.C.
3280	Lime
3382	Lime
3444	Lime
3471	Arbuckle
3520	Arbuckle

COPY

RECEIVED
STATE CORPORATION COMMISSION

I certify the above to be a true and correct copy of the
drillerslog to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

K. T. Woodman
K.T. Woodman, Partner

FEB 05 1992
CONSERVATION DIVISION
WICHITA, KANSAS