

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-051-23,042 0000 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Zinszer Oil Company OPERATOR'S LICENSE NO. 6239 6-92

ADDRESS 206 W. 26th, Hays, KS 67601 PHONE # (913) 625-6246/625-9448

LEASE (FARM) Simpson WELL NO. 3 WELL LOCATION 80'N SW NW SE COUNTY Ellis
SEC. 15 TWP. 11 RGE. 17 (E) or (W) TOTAL DEPTH 3520' PLUG BACK TD 3415'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 259' CEMENTED WITH 165 SACKS

CASING SIZE 5 1/2" SET AT 3516' CEMENTED WITH 150 SACKS
below plug below plug above plug

PERFORATED AT & squeezed: 3429-56, & open: 3442-45, & open: 3371-72, 3338-39, 3315-16,
& 3137-39

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Perforate Anhydrite, spot cement through tubing, pull
tubing, squeeze cement down casing until circulates out backside, if cement doesnot
circulate then squeeze down backside.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN On or after 2/8/92

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:


Perry S. Henman PHONE # (913) 726-3768 or 625-6246

ADDRESS 206 W. 26th, Hays, Kansas 67601

PLUGGING CONTRACTOR Allied Cementing LICENSE NO. _____

ADDRESS P.O. Box 31, Russell, KS 67665 PHONE # (913) 483-26

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: 
(Operator or Agent)

DATE: 2/3/92

4

RECEIVED
STATE CORPORATION COMMISSION
FFB 05 1992
CONSERVATION DIVISION
WICHITA, KANSAS



Kansas Corporation Commission

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

February 5, 1992

Zinszer Oil Company
206 W 26th
Hays KS 67601

Simpson 3
API 15-051-23,042
80' N SW NW SE
Sec. 15-11-17W
Ellis County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200

Conservation Division
William R. Bryson
Director

200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238