

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

RECEIVED

FEB 10 1982

WELL PLUGGING RECORD

CONSERVATION DIVISION
Wichita, Kansas

Give All Information Completely
Make Required Affidavit

COUNTY Ellis SEC. 16 TWP. 11S RGE. 17W E/W
Location as in quarters or footage from lines:
SE SW NE

Locate Well
correctly on above
Section Platt.

Lease Owner Liberty Enterprises, Inc.
Lease Name Mariana #1 Well No. _____
Office Address 308 W. Mill Street Plainville, Kansas 67663
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 1-20-82
Plugging completed 1-22-82
Reason for abandonment of well or producing formation _____

_____ Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
Producing formation _____ Depth to top _____ bottom _____ T.D. 3424' AUG
Show depth and thickness of all water, oil and gas formations. 3414' KCC

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1051'	none
				4-1/2"	3398'	2447'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3000' and set 4 sacks cement. Shot casing @2742', 2550' and 2448'. Pulled a total of 60 joints of pipe. Plugged well with 5 sacks hulls, 20 sacks gel, 8-5/8" plug, 140 sacks 50/50 pos, 4% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of February, 19 82

My Commission expires:



Irene Hoover
Notary Public.

CONTRACTOR'S WELL LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:
COMMENCED:
COMPLETED:

OKMAR OIL COMPANY
LEBEN DRILLING, INC.
(BEMIS #1) MARIANNA (owwo)
SE SW NE SEC. 16-11S-17W
ELLIS COUNTY, KANSAS
7-14-57
7-24-57

0	40	Sand & Clay
40	460	Sand, Ft. Hays Lime & Shale
460	475	Shale
475	540	Sand & Purite
540	730	Shale
730	850	Redbed & Shells
850	1045	Redbed
1045	1100	Anhydrite
1100	1200	Redbed & Shells
1200	1530	Shale & Shells
1530	2865	Shale & Lime
2865	2955	Lime & Shale
2955	3325	Lime
3325	3345	Conglomerate
3345	3375	Lime & Shale
3375	3416	Conglomerate
	3416	<u>Rotary Total Depth - D & A</u>

Set 6 5/8" surface casing at 1051' with 500 sacks cement & 2% CaCl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Bemis #1, SE SW NE Section 16, Township 11 South, Range 17 West, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

By: Frank Hamlin
Frank Hamlin

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss.

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 19th day of September, 1957.

Ruth H. Benjamin
Ruth H. Benjamin - Notary Public

My commission expires June 17, 1961.

