


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 16 Twp. 11 Rge. (E) 17 (W)

Location as "NE/CNW&SW&" or footage from lines NW NW NE/4  
Lease Owner Herman George Kaiser, Oil Producer  
Lease Name Bemis D Well No. 1  
Office Address 909 Palace Bldg., Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed June 15, 1960  
Application for plugging filed June 15, 1960  
Application for plugging approved June 15, 1960  
Plugging commenced June 15, 1960  
Plugging completed June 15, 1960  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3381 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1055	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

MUDDED HOLE TO 400 FT., SET PLUG AND CEMENTED WITH 20 SACKS CEMENT THROUGH DRILL PIPE. MUDDED HOLE TO 180 FT., SET PLUG AND CEMENTED WITH 20 SACKS CEMENT THROUGH DRILL PIPE. MUDDED HOLE TO 40 FT., SET PLUG AND CEMENTED WITH 1/2 SACK HULLS AND 10 SACKS CEMENT TO SURFACE.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 28 1960  
06-28-60  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet.)

Name of Plugging Contractor H-30, Inc.  
Address 709 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick  
L. C. Sponenberg <sup>employee of contractor</sup> (employee of owner or contractor or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 27th day of June, 19 60

Rose Furey  
Rose Furey, Notary Public.

My commission expires February 13, 1964



15-051-03766-0000

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **HERMAN GEO. KAISER**  
FARM **BEMIS D** NO. **1**

SEC. **16** T. **11** R. **17W**  
LOC. **NW NW NE/4**

TOTAL DEPTH **3381'**  
COMM. **6/1/60** COMP. **6/15/60**  
SHOT OR TREATED **—**  
CONTRACTOR **H-30, Inc.**  
ISSUED

COUNTY **Ellis**

KANSAS



CASING	
20	10
15	8 1055'
12	6
13	5

ELEVATION **1814 K.B.**  
**1811 D.F.**  
**1809 G.L.**  
PRODUCTION **D+7**

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Rock & Clay	95'
Shale	397'
Dakota Sand	540'
Sand	685'
Shale & Shells	1035'
Shale	1046'
Plug & Cement	1055'
Anhydrite	1095'
Shale	1411'
Shale	1745'
Lime & Shale	2260'
Lime with Shale Streaks	2379'
Shale & Lime	2700'
Shale	2738'
Lime with Shale Streaks	2787'
Lime & Shale	2847'
Lime	3094'
Kansas City Lime	3145'
Lime	3255'
Kansas City Lime	3292'
Lime	3300'
Conglomerate	3350'
Lime & Shale, Chert	3375'
Arbuckle	3381'

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUN 28 1960  
CONSERVATION DIVISION  
Wichita, Kansas

FORMATION TOPS:

Heebner	2990 -1176
Kansas City	3034 -1220
Arbuckle	3374 -1560

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By L. C. Sponenberg  
L. C. Sponenberg

STATE OF KANSAS )  
( SS:  
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 27th day of June, 1960.

My Commission expires February 13, 1964. Rose Furey  
Rose Furey, Notary Public