


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

original to SCC 1/26/60
15-051-03765-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Ellis County. Sec. 16 Twp. 11 Rge. 17 (E) 17 (W)

Location as "NE/CNW%SW%" or footage from lines. NW NE SW 1/4

Lease Owner Herman Geo. Kaiser, Oil Producer

Lease Name Bemis Well No. 1

Office Address 909 Palace Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed Jan. 15 1960

Application for plugging filed Jan. 15 1960

Application for plugging approved Jan. 15 1960

Plugging commenced Jan. 15 1960

Plugging completed Jan. 15 1960

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3403 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1088 1/2	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH ROTARY MUD TO 400 FT., SET PLUG AND CEMENTED WITH 20 SACKS CEMENT THROUGH DRILL PIPE. MUDDED HOLE TO 180 FT., SET PLUG AND CEMENTED WITH 20 SACKS CEMENT. MUDDED TO 40 FT., SET PLUG AND CEMENTED WITH 10 SACKS CEMENT TO AND 1/2 SACK HULLS

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1960
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
JAN 26 1960
HERMAN GEO. KAISER
OIL PRODUCERS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 709 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick
L. C. Sponenberg (employee of contractor) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg

SUBSCRIBED AND SWORN TO before me this 20th day of January, 1960

My commission expires February 13, 1960

Rose Furey
Rose Furey
Notary Public.



15-051-03765-0000
original to SCC 1/26/60

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Herman Geo. Kaiser, Oil Producer**

SEC. 16 T. 11 R. 17 W

FARM **Bemis**

NO. 1

LOC. **NW NE SW $\frac{1}{4}$**

TOTAL DEPTH **3403'**

COUNTY **Ellis**

COMM. **1/5/60**

COMP. **1/16/60**

RECEIVED
STATE CORPORATION COMMISSION


KANSAS

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED

JAN 27 1960



CONSERVATION DIVISION
Wichita, Kansas

CASING

20	10	
15	8	1088 1/2'
12	6	
13	5	

ELEVATION **1851 K. B.**
1848 D. F.
1846 C.

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay & sand	25'
Shale	395'
Sand	420'
Shale & shells	598'
Sand	735'
Shale & shells	765'
Shale & shells & red-bed	980'
Streak of Pyrite 967-974	
Red bed - shale & shells	1,083'
Anhydrite	1,089'
Anhydrite	1,115'
Shale & shells	1,470'
Shale & salt lime	1,755'
Lime & shale	3,087'
Kansas City Lime	3,145'
Lime & shale	3,200'
Kansas City Lime	3,337'
Lime, shale & chert	3,403'

RECEIVED
JAN 26 1960
HERMAN GEO. KAISER
OIL PRODUCERS

FORMATION TOPS:

Topeka	2813 -962
Heebner	3045 -1194
Toronto	3067 -1216
Lansing Kansas City	3089 -1238

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *L. C. Sponenberg*
L. C. Sponenberg

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 20th day of January, 1960.

Rose Furey
Rose Furey, Notary Public

My Commission expires February 13, 1960.