

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-02181-0000

API NUMBER 6/11/36

LEASE NAME Bemis A

WELL NUMBER #2

990 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 16 TWP. 11 RGE. 17 (X) or (W)

COUNTY Ellis

Date Well Completed 6/11/36

Plugging Commenced 9/22/94

Plugging Completed 9/22/94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Zinszer Oil Company, Inc

ADDRESS P.O. Box 211, Hays, Kansas 67601

PHONE# (913) 625-9448 OPERATORS LICENSE NO. 6239

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Before 9/22/94 (date)

by Dennis Hammel (Hays) (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation Topeka, LKC, Arb. Depth to Top 2964 Bottom 3371 T.D. 3371

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Topeka	oil & water	82	12	15 1/2	70	-0-
LKC	oil & water	1063	10	13 3/8	1053	-0-
Arbuckle	oil & water	3361	0	7	3361	4

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 7/9/58 CIBP @ 3320', 7/27/82 squeezed perfs. (2964 - 3255) from 2820' with 300sx common, 7/29/82 squeezed casing leak (holes between 1688 & 2209') with 500sx 60/40poz, and 400sx common, 9/22/94 perf. 3 shots @ 1053, pumped thru tubing @ 1650' with 330sx 40/60poz 6% gel, cement circ.out 7", pull tubing, pumped
(If additional description is necessary, use BACK of this form.) over

Name of Plugging Contractor Halliburton License No. _____

Address Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zinszer Oil Company, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Perry S. Henman

(Employee of Operator) Operator of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 211, Hays, Kansas

WITNESSED AND SWORN TO before me this 29th day of September, 1994



Robert J. Schibi

Notary Public

My Commission Expires: August 24, 1998

130sx 40/60poz down casing, cement circ. out 13 3/8", shut in
pressure 300#.

Note: well record indicates 34' fill and a 12' mud anchor
on top of CIBP.