

RECEIVED

JUL 19 2010

Form CP-4
March 2009

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD
K.A.R. 82-3-117

KCC WICHITA

Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5135
Name: John O. Farmer, Inc.
Address 1: P.O. Box 352
Address 2: _____
City: Russell State: KS Zip: 67665 + 0 3 5 2
Contact Person: Marge Schulte
Phone: (785) 483-3145, Ext. 214
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3674' Bottom: 3740' T.D. 3740' RTD
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - -065-23,344 19000
Spot Description: _____
SW NW, NE, NE Sec. 31 Twp. 7 S. R. 21 East West
520 Feet from North / South Line of Section
1,170 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Graham
Lease Name: Van Loenen "B" Well #: 1
Date Well Completed: 10-16-07
The plugging proposal was approved on: prior to plugging (Date)
by: District #4 (KCC District Agent's Name)
Plugging Commenced: 12:00 P.M., 7-9-10
Plugging Completed: 1:00 P.M., 7-9-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Arbuckle (perms. 3683-92')	oil & water	surface	8-5/8"	221'	-0-
		production	5-1/2"	3738'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 100 sks. cement w/250# hulls @ 3670'; mixed 100 sks. cement w/100# hulls @ 2700'; mixed 135 sks. cement @ 1750' to circulate cement. Mixed 15 sks. cement down 5-1/2" casing to top off. Mixed 10 sks. cement down backside to 200 PSIG and shut in.

TOTAL: 360 sks. 60/40 Pozmix & 350# hulls

Plugging Contractor License #: _____ Name: Allied Cementing Company, LLC.
Address 1: P.O. Box 31 Address 2: _____
City: Russell State: Kansas Zip: 67665 + 0 0 3 1
Phone: (785) 483-2627

Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.
State of Kansas County, Russell, ss.
John O. Farmer III, President of John O. Farmer, Inc. Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature] 7-16-10

ALLIED CEMENTING CO., LLC. 041662

COPY

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell KS

DATE <u>7-9-10</u>	SEC <u>31</u>	TWP <u>7</u>	RANGE <u>21</u>	CALLED OUT	ON LOCATION	JOB START <u>12:00pm</u>	JOB FINISH <u>1:00pm</u>
Van Loenen "B" LEASE	WELL #/	LOCATION: <u>Bogue North to 24 Hwy 1 North</u>			COUNTY <u>Graham</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)		<u>to S Rd 1 West 1/2 South West into.</u>					

CONTRACTOR: <u>Poc Servicing</u>	OWNER	
TYPE OF JOB: <u>PTA</u>	<u>(used 360sk cement and 380# Hulls)</u>	
HOLE SIZE	T.D.	CEMENT
CASING SIZE <u>5 1/2</u>	DEPTH <u>3700'</u>	AMOUNT ORDERED <u>450 6940 4% Gel</u>
TUBING SIZE <u>2 3/8</u>	DEPTH <u>3670'</u>	<u>500# Hulls</u>
DRILL PIPE	DEPTH	
TOOL	DEPTH	
PRES. MAX	MINIMUM	COMMON <u>2 1/2 @ 1750 2916.00</u>
MEAS. LINE	SHOE JOINT	POZMIX <u>7 1/4 @ 7.55 1087.20</u>
CEMENT LEFT IN CSG.		GEL <u>12 @ 20.25 243.00</u>
PERFS.		CHLORIDE @
DISPLACEMENT		ASC @

EQUIPMENT

PUMP TRUCK: CEMENTER <u>John Roberts</u>	
# <u>398</u> HELPER <u>Paul</u>	
BULK TRUCK	
# <u>394/297</u> DRIVER <u>Jerry</u>	
BULK TRUCK	
# DRIVER	
HANDLING <u>560 @ 2.25 1240.00</u>	
MILEAGE <u>19 1/4 @ 1940.00</u>	
TOTAL <u>6496.20</u>	

REMARKS:

Mix 100sk w/ 250# Hulls @ 3670'
Mix 100sk w/ 100# Hulls @ 2700'
Mix 125sk @ 1750' to circulate cement
Mix 15sk down 5 1/2 casing to top of
Mix 10sk down back side to 200ps
and shut in.
Thank You!

SERVICE

DEPTH OF JOB	
PUMP TRUCK CHARGE	<u>875.00</u>
EXTRA FOOTAGE @	
MILEAGE <u>190 @ 7.00 1330.00</u>	
MANIFOLD @	
TOTAL <u>1155.00</u>	

CHARGE TO: John O Farmer

STREET _____
CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

To Allied Cementing Co., LLC
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (If Any)	
TOTAL CHARGES	
DISCOUNT	
IF PAID IN 30 DAYS	

PRINTED NAME _____

SIGNATURE John O Farmer

RECEIVED
JUL 19 2010
KCC WICHITA