

*Handwritten signature*

RECEIVED

JUL 19 2010

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD KCC WICHITA K.A.R. 82-3-117

Form CP-4 March 2009

Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 34318 Name: BEREXCO LLC Address 1: PO BOX 723 Address 2: PO BOX 20380 - WICHITA, KS 67206 City: HAYS State: KS Zip: 67601 Contact Person: MARK LEIKER Phone: (316) 772-8649 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) 4529 Depth to Top: 4535 Bottom: T.D.

API No. 15 - 135-22530-0000 Spot Description: NW SW SE Sec. 3 Twp. 16 S. R. 25 East West 990 Feet from North / South Line of Section 2,310 Feet from East / West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: NESS Lease Name: REUSSER Well #: 1 Date Well Completed: 5/11/84 The plugging proposal was approved on: 6/29/10 (Date) by: RICHARD LACEY (KCC District Agent's Name) Plugging Commenced: 6/29/10 Plugging Completed: 6/29/10

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows include MISS SURFACE and PRODUCTION.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TIH w/2 3/8 workstring to 4400'. Pump 15 sx gel and 30 sx 60/40 POZ cement w/4% gel and 150# hulls. Pull tbg to 2005' & pump 130 sx 60/40 POZ cement w/4% gel and 200# hulls. Pull up to 1058'. Pump 160 sx 60/40 POZ cement w/4% gel and circulated cement to surface. TOH w/tbg. Top off w/60 sx 60/40 POZ cement. Tie onto 8 5/8 and pump 80 sx 60/40 POZ w/4% gel. Rig down. Job witnessed by KCC. Top off casing 25 sx cement. Cut off casing. Back fill. Clean up. Well is plugged.

Plugging Contractor License #: 34318 Name: BEREXCO LLC Address 1: PO BOX 723 Address 2: PO BOX 20380 - WICHITA, KS 67206 City: HAYS State: KS Zip: 67601 Phone: (785) 628-6101 Name of Party Responsible for Plugging Fees: BEREXCO LLC State of KANSAS County, SEDGWICK, ss. MARK LEIKER (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Leiker