

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

JUL 19 2010

Form CP-4 March 2009

Type or Print on this Form Form must be Signed All blanks must be Filled

WELL PLUGGING RECORD KCC WICHITA K.A.R. 82-3-117

OPERATOR: License #: 6131 Name: Drillers & Producers, Inc. Address 1: P.O. Box 385 City: Newton State: Ks Zip: 67114 Contact Person: Bill Hanson Phone: (316) 841-0022 Type of Well: Oil Well Water Supply Well ENHR Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet)

API No. 15 - 115-20763 Spot Description: ne-nw Sec. 28 Twp. 21 S. R. 4 East West 5,204 Feet from North South Line of Section 2,832 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Marion Lease Name: Deforest B Well #: 3 Date Well Completed: Feb. 1983 The plugging proposal was approved on: March 2, 2010 by: Steve Bond Plugging Commenced: 3-31-2010 Plugging Completed: 3-31-2010

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows include surface casing (8 5/8" size, 200' depth) and production casing (5 1/2" size, 2388' depth, 323' pulled out).

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2.5" tubing to 2377', circulated water to surface, pumped 35 sx common cement w/3% cc, ran wire line and tagged plug @ 2108', shot off casing at 323' and pulled, ran in 2.5" to 268', circulated cement to surface, used 120 sx of 60/40 pos w/4% gel, pulled tubing and topped off

Plugging Contractor License #: 5870 Name: Phillips Well Service, Inc. Address 1: P.O. Box 1263 City: El Dorado State: Ks Zip: 67042 Phone: (316) 321-6650

Name of Party Responsible for Plugging Fees: Drillers & Producers, Inc. State of Ks County, Harvey, ss. Bill Hanson (Print Name) Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Bill Hanson