

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Ken L Cody
Address: 1125 Road 27, Longton, Kansas 67352
Phone: (620) 642-6123 Operator License #: 7786
Type of Well: Oil Docket #: n/a
The plugging proposal was approved on: June 18, 2010
by: KCC- Wichita
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): Burgess Depth to Top: 1570 Bottom: 1582 T.D. 1594

API Number: 15-049-22053-0000
Lease Name: Barnaby-Glory
Well Number: Glory #1
Spot Location (QQQQ): SE - NW - SE - SE
710 Feet from North / South Section Line
1000 Feet from East / West Section Line
Sec. 18 Twp. 30 S. R. 13 East West
County: Elk
Date Well Completed: 1-23-1988
Plugging Commenced: June 23, 2010
Plugging Completed: June 23, 2010

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows include Big Salt, Layton, KC Lime, and Burgess.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

53' cement plug from TD (1594) to 1541'--Gel from 1541' to 850'; Cement plug from 850' to 800'--Gel from 800' to 350'; Cement from 350' to Surface. Cemented through 2" tubing to spot plugs. Shot hole in casing at 850' and 350'

Name of Plugging Contractor: Elmore's Inc. License #: 32884
Address: Box 87, 776 Highway 99, Sedan, Kansas-67361
Name of Party Responsible for Plugging Fees: Ken L. Cody
State of Kansas County, Elk


RECEIVED JUL 15 2010

Ray Ebberts (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Ray Ebberts
(Address) 3342 SW Friar Rd. Topeka, Kansas 66614

SUBSCRIBED and SWORN TO before me this 13 day of July 20 10
Kathy A. Brown My Commission Expires: 2/25/2014

Notary Public



KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

8685

**STATEMENT**

**ELMORE'S INC.**  
 Box 87 - 776 HWY99  
 Sedan, KS 67361  
 Cell: (620) 249-2519  
 Eve: (620) 725-5538

Date **6-23-10**

Customer Ken Cody  
 Address \_\_\_\_\_  
 City \_\_\_\_\_ State \_\_\_\_\_ Zip \_\_\_\_\_

Qty.	Description	Price	Amount
4	hr Cement Pump	100.00	400.00
4	hr Water Truck	80.00	320.00
1	Bank Tank	80.00	80.00
2	Sks Coel	15.00	30.00
55	Sks Cement	8.25	453.75
			\$ 1283.75
	Plus Job Barmanbe Tax		80.88
	City #1 Coel Hole		\$ 1364.63
	1500' 4 1/2 Casing Spotted		
	10 Sks Cement at Bottom		
	Pulled Tubin Shot Holes In		
	Casing At 850 + 350 Ran		
	Tubin In To 850 Spotted		
	10 Sks Cement Pulled Tubin Up		
	To 350 Cemented To Surface With		
	35 Sks Cement		
	Paid in full 7-13-10		

Thank You -- We appreciate your business!

h779  
 RECEIVED  
 P.O.A.  
 JUL 15 2010

Rec'd. by \_\_\_\_\_

TERMS: Account due upon receipt of services. A 1 1/2% Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.

KCC WICHITA