

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31930
Name: BlueRidge Petroleum Corporation
Address 1: P.O. Box 1913
Address 2: _____
City: Enid State: OK Zip: 73702 + 1913
Contact Person: Jonathan Allen
Phone: (580) 242-3732
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Lansing H Depth to Top: 3746 Bottom: 3752 T.D. _____
Lansing J Depth to Top: 3782 Bottom: 3787 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 179-21254-00-00
Spot Description: _____
SE NE SE SE Sec. 18 Twp. 8 S. R. 26 East West
790 Feet from North / South Line of Section
140 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Sheridan
Lease Name: TJ Well #: 1-18
Date Well Completed: 05/15/2010
The plugging proposal was approved on: 08/19/2010 (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 08/23/2010
Plugging Completed: 08/23/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	221	0
		Production	5.50	3885	2485

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 50 sx w/ 100# hulls @ 2142', 100 sx w/ 200# hulls @ 1541', 40 sx @ 263' & 30 sx @ 113' w/ cement to surface. Total cement 220 sx 60/40 Poz w/ 4% gel. P&A'd 08/23/2010.

RECEIVED

SEP 17 2010

KCC WICHITA

Plugging Contractor License #: 6426 Name: Express Well Service & Supply Inc.

Address 1: P.O. Box 19 Address 2: _____

City: Victoria State: KS Zip: 67671 + 0019

Phone: (785) 735-9405

Name of Party Responsible for Plugging Fees: BlueRidge Petroleum Corporation

State of Oklahoma County, Garfield, ss.

Jonathan Allen Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: