

*Handwritten signature*

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 32446 Name: Merit Energy Company Address 1: 13727 Noel Rd., Suite 500 Address 2: City: Dallas State: TX Zip: 75240 Contact Person: Lynne Moon /Regulatory Manager Phone: (972) 628-1569 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: S SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D.

API No. 15 - 175-20813-00-02 Spot Description: Sec. 11 Twp. 32 S. R. 34 East West Feet from North South Line of Section East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Seward Lease Name: E. Paul Boles Well #: 4-11 Date Well Completed: The plugging proposal was approved on: 9/14/10 by: Steve Pfeiffer (KCC District Agent's Name) Plugging Commenced: 9/14/10 Plugging Completed: 9/16/10

Pen GB 9/16/10 Ken

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows include Surface (8 5/8", 1679') and Production (5 1/2", 5839').

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TIH w/ 5 1/2" tbg set CIBP to 5416', set CIBP & circ hole w/ mud, spot 5 sks cement on CIBP. Weld on pull sub, cut csg 4 times at 1) 1780', 2) 1735', 3) 1170' & 4) 776', could not pull csg. Run tbg @ 3024' & spot 25 sks Class "C" cement up to 2777' to cover DV Tool @ 3003'. POH w/ tbg. Run Pkr @ 1200' & pressure to 1200 psi, could not pump in cuts. Pull Pkr to 600' & pressure top cuts, could not pump in. POH w/ Pkr & TIH open ended to 1820' & spot 30 sks Class "C" cement up to 1520', Pull up hole w/ tbg @ 1200' & circ to surface w/ 120 sks cement. POH w/ tbg & RU down 8 5/8", pump 7 sks cement & pressure to 300 psi. Leave full to surface.

Plugging Contractor License #: 33338 Name: ORR ENTERPRISES, INC. Address 1: P.O. Box 1706 Address 2: City: Duncan State: Oklahoma Zip: 73534 Phone: (580) 467-0258

Name of Party Responsible for Plugging Fees: MERIT ENERGY COMPANY State of TEXAS County: DALLAS, ss. Lynne Moon (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Lynne Moon

RECEIVED SEP 22 2010