

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5225
Name: Quinque Operating Company
Address 1: 908 NW 71st Street
Address 2: _____
City: Oklahoma City State: OK Zip: 73116 + _____
Contact Person: Catherine Smith
Phone: (405) 840-9876 Ext. 129
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
5511' Depth to Top: 5513' Bottom: _____ T.D. _____
5550' Depth to Top: 5554' Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 175-20991-00-01
Spot Description: 26
C SW SW 23 Twp. 33 S. R. 32 East West
1,220 Feet from North / South Line of Section
3,760 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Seward
Lease Name: City of Liberal Well #: 1-26
Date Well Completed: Dec. 20, 1987
The plugging proposal was approved on: 8/13/10 approved (Date)
by: Jerry Stapleton (KCC District Agent's Name)
Plugging Commenced: 8/17/2010
Plugging Completed: 8/18/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	1601	0
		Production	4 1/2	5854	1705

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 40 bbls mud down csg. TIH w/ CIBP on tbg. Set at 5455'. Pumped 10 sxs cmt on top. Shot 4-1/2 csg at 1705'. Layed down same. TIH with tbg to 1650'. Pumped 200# cotton seed hulls. Pumped 50 sxs cmt. TOH to 500'. Pumped 30 sxs cmt. TOH to 60'. Pumped 15 sxs cmt to surface. Cut wellhead off 4' below ground level.

Plugging Contractor License #: 33311 Name: Phil Dollar Oilfield Services, Inc.
Address 1: P.O. Box 744 Address 2: _____
City: Perryton State: TX Zip: 79070 + 0744
Phone: (806) 435-3373
Name of Party Responsible for Plugging Fees: Quinque Operating Company
State of Oklahoma County, Oklahoma, ss.
Catherine Smith Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Catherine Smith