



15-051-22736-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Tom Aom of Pioneer Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Liberty Enterprises Inc.

Complete Address: 308 W. Mill, Plainville, Ks. 67663

Lease Name: Gail Well No. 1

Location: NW NE SW Sec. 10 Twp. 11 Rge. 17 (E) (W)

County: Ellis Total Depth: 3450'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Tom Aom was instructed to plug the well as follows:

8 5/8" 366' S.P. cuc. W/ 170 sacks 60/40 posmix 2% Gel-3%Cal.Cl.

Ordered 130 sacks 50/50 posmix 4% Gel-3%Cal.Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' W/ 70 sacks cement

2nd plug @ 310' W/ 40 sacks cement

3rd plug Solid bridge of hulls and plug @ 40' W/ 10 sacks cement

Circulate 10 sacks cement in rat hole.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

[Signature]
JAN 11 1982
01-11-82
CONSERVATION DIVISION
Conservation Division Agent Wichita, Kansas