

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 15-051-02161-0001
13-18

LOCATION SE SW SW

SEC. 14 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. A-2 Lease Hall

Operator Cities Service Co Address Great Bend, Kans

Field Bemis County Ellis

Total Depth 3450 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4"vat 1102' circulated with 400 sax cement - 7" at 3381'
with 275 sax cement behind - 131' 5 1/2" liner in bottom
cemented in. Lane Wells plugs to 3411' - top perforations at
3399'.

Filled with sand to 3350', set 5 sax cement with dump bailer,
pulled 2640' 7" - filled with mud to 350', set rock bridge and
20 sax cement - filled with mud to 35', set rock and 10 sax
cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1952

[Signature]
District Conservation Agent

Date 5-14-52

PLUGGING

FILE SEC 14 T 11 R 17
BOOK PAGE 13 LINE 18

CONSERVATION DIVISION
Wichita, Kansas
05-16-52