

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 69-2 (15-051-02164-0000)

LOCATION NE SE SW

SEC. 14 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. A-5 Lease Hall

Operator Cities Service Co Address Russell, Kans

Field Bemis County Ellis

Total Depth 3367 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1075' with 335 sax cement behind - 5 1/2" at 3362'  
with 100 sax behind - 5 1/2" squeezed at 2040' with 600 sax cement.  
Dumped 5 sax cement in bottom with dump bailer - pulled 1570'  
5 1/2" - filled hole with heavy mud to 250', set rock bridge  
and 15 sax cement - filled with mud to 35', set rock and 10 sax  
to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 2 - 1951

CONSERVATION DIVISION  
Wichita, Kansas

[Signature]  
District Conservation Agent

Date 4-30-51

PLUGGING  
FILE SEC 14 T 11 R 17 W  
BOOK PAGE 69 LINE 8