

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 15 1962

CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis 15-051-02167-0000

Location: SE SW SE Sec. 14 Twp. 11 Rge. (E) (W) 17

Name of Field: _____ Total Depth: 3380

I have this date completed supervision of plugging of:

Lease Name: Henry Mai DWB rcc Well No. 3

Operator's Full Name: Great Bend Pipe & Supply

Complete Address: Drawer B Great Bend, Kansas

Plugging Contractor Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 11 Day 6 Month _____ Year 62

The above well was plugged as follows:

16" 52' circulated - 9 5/8" 1096' circulated with cement - 7" 3374' with
150 sax cement behind - filled with sand to 3360', set 5 sax cement
with dump bailer - pulled 2414' 7" - filled hole with heavy gel mud
to 450', set 25 sax cement at 450', heavy gel mud to 160', set 25 sax
cement at 160', heavy mud to 25', cement to bottom cellar, (used
27 sax Gel)

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 6/15/62
INV. NO. 5187-W