

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

15-051-02180-0000
FILE NO. 62-9

LOCATION CN $\frac{1}{2}$ NE SE

SEC. 14 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 9 Lease H. Mai ANB KCC

Operator Gulf Oil Corp Address Box 225 Great Bend, Kans

Field _____ County Ellis

Total Depth 3367 Feet.

Plugging Contractor C.E. Shull Pipe Pulling

Plugging Contractor's License No. 8

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 1057' circulated with 525 sax cement - 5 1/2" at 3359'

with 115 sax cement behind.

Filled with sand to 3340', set 4 sax cement with dump bailer,

pulled 2680' 5 1/2" - filled hole with heavy mud to 300', set rock

and 25 sax cement, mud to 35', set rock and 10 sax cement to

bottom cellar.

Edwin Lett
District Conservation Agent

Date 5-23-56

PLUGGING
FILE SEC 14 T. 11 R. 17W
BOOK PAGE 62 LINE 9

STATE OF KANSAS
05-25-56
CONSERVATION DIVISION