

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
 Conservation Division  
 800 Bitting Building  
 Wichita, Kansas

FILE NO. 29-12  
 LOCATION SW SW NW  
 SEC. 15 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. B-1 Lease E.A. Bemis AWB KCC  
 Operator The Texas Co Address Wichita, Kans  
 Field Bemis County Ellis  
 Total Depth 3424 Feet.

(Describe briefly the manner in which the well was plugged)

16" at 120' circulated with cement - 10" at 1112' circulated  
with cement - 7" at 3421' with 100 sax cement behind.  
7" squeezed at 2820' with 150 sax cement - cement and  
Baker plugs to 2970', top perforations at 2911'.  
Filled with chat tom 2900', set 5 sax cement with dump  
bailer, pulled 2291' 7", filled hole with mud to  
300', set rock bridge and 25 sax cement, mud to 55',  
set rock and 15 sax cement to bottom cellar.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 PLUGGING  
 JUL 16 1952  
 CONSERVATION DIVISION  
 Wichita, Kansas

*J. Edgar Petty*  
 District Conservation Agent  
 Date 7-14-52