

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 13-17

LOCATION SE SE SW

SEC. 15 TWP. 11 RGE. 17W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. B-7 Lease *John* Bemis

Operator Sohio ~~Oil~~ Co Address Russell, Kans

Field _____ County Ellis

Total Depth 3421 Feet.

Plugging Contractor Miller Casing Pulling

Plugging Contractor's License No. 12

Address _____

(Describe briefly the manner in which the well was plugged)

15" at 35' - 10" at 1128' circulated with 300 sax cement - 7" atn
3417' with 150 sax cement behind - squeezed at 2600' with 200 sax
cement.

Filled with chat to 3400', set 4 sax cement with dump bailer,
pulled 1450' 7" casing - filled with heavy mud to 300', set rock
and 25 sax cement, mud to 35', set rock and 10 sax cement to bottom
cellar.

Edwin Perry
District Conservation Agent

Date 11-20-55

REC'D
11-22-55
DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC 15 TWP 11 R 17W
BOOK PAGE 13 LINE 27