


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 118-38
720' from West Line & 400' North of South line
LOCATION SE 1/4 CS/2 SWSE
SEC. 15 TWP. 11 RGE. 17

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. X 1 Lease Richmond
Operator Aylward Drg Co Address Wichita, Kans
Field Bemis County Ellis
Total Depth ~~3472~~ 3462 ANBKCC Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 153' circulated with cement.

Circulated hole with heavy mud, pushed cementing plug to
150', displaced 20 sax cement through drill pipe, heavy mud to
40', set cementing plug, 1/2 sack hulls and filled hole to bottom
cellar with cement.

PLUGGING
FILE SEC 15 T 11 R 17
BOOK PAGE 118 LINE 38

[Signature]
District Conservation Agent
Date 10-21-51

STATE CORPORATION COMMISSION
OCT 27 1951
CONSERVATION DIVISION
Wichita, Kansas