

MP
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morgenstern - Specter
Complete Address: Box 661 Russell, Kansas
Lease Name Richmand Well No. 1
Location SW SE SE Sec. 15 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3416
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Ralph Lynch
Address: Great Bend, Kans License No. 457
Operation Completed: Hour 6 PM Day 14 Month 10 Year 63

The Above well was plugged as follows:

10 3/4' 820' circulated with cement - 7" 3395' with 150 sax cement
PB with chat to 3000', set 5 sax cement with dump bailer - pulled
1585' 7" to 500', circulate hole with heavy gel mud - displaced 25
sax cement through 7" at 500', heavy mud to 200', displaced 25 sax
cement through 7" at 200', heavy mud to 25', set 10 sax cement
to bottom cellar.

Mudding and cementing by Lynch Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Leon P. [Signature]*
Well Plugging Supervisor

DATE 10/16/63
INV. NO. 4905-W