

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1962
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Rudy Herman
Complete Address: Russell, Kansas Box 348
Lease Name Richmond Well No. 1
Location SW ^{NW} SE Sec. 15 Twp. 11 Rge. (E) (W) 17
County Ellis ^{ANBCC} Total Depth 3511
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Barnes & Sons
Address: Russell, Kans License No. 9
Operation Completed: Hour 1PM Day 22 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 226' circulated with cement - 5 1/2" 3511' with 125 sax cement - PB to 3470' - perforated 3223'.
Filled with sand to 3210', set 5 sax cement with dump bailer, pipe eaten into at 600' - pulled 5 1/2" to 525', circulated hole with heavy mud through 5 1/2" at 525' (22 sax Gel), displaced 20 sax cement through 5 1/2" as 525', heavy mud to 180', displaced 20 sax cement through 5 1/2", heavy mud to 30', cement 30' to 0'.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/29/62
INV. NO. 5435-W

Signed: [Signature]
Well Plugging Supervisor