

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1963
10-15-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Morganstern * Specter

Complete Address: Russell, Kansas

Lease Name Richmond#2 Well No. 2

Location SE SE SE Sec. 15 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3410

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Ralph Lynch

Address: Great Bend, Kans License No. 457

Operation Completed: Hour 4PM Day 11 Month 10 Year 63

The Above well was plugged as follows:

10 3/4" 1015' circulated with cement - 7" 3396' cemented & squeezed
approx - 2600'

Sand back to 3000', set 5 sax cement with dump bailer - pulled 1580' 7"
to 500', circulated hole with heavy gel mud at 500', displaced 25 sax
cement through 7" at 500', heavy gel mud to 200', displaced 25 sax
cement through 7" at 200', heavy mud to 30', set bridge and cement to
bottom cellar.

Mudding and cementing by Lynch Company Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10/15/63
INV. NO. 9899-w

Signed: [Signature]
Well Plugging Supervisor