

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051 -21,367 -0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Zinszer Oil Co.

Complete Address 206 W. 26th St., Hays, Ks. 67601

Lease Name Simpson Well No. 1

Location W/2 W/2 SE Sec. 15 Twp. 11 Rge. 17 (East) ~~(West)~~

County Ellis Total Depth 3464'

Abandoned Oil Well XXXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Packer @ 809' can't be recoverd

Plugging Contractor Rockhold Engineering, Inc.

Address P.O. Box 698, Great Bend, Ks. 67530 License No.

Operation Completed: Hour: 11:30 PM Day: 26 Month: 4 Year: 19 82

Plugging Operations attended by Agent?: All XXXX Part None

The above well was plugged as follows:

8 5/8"-243' S.P. cuc. w/175 sacks common. 5 1/2" casing set @ 3463' w/100 sacks
common. Top perf. @ 3420'. Ordered 250 sacks 50/50 posmix-4% Gel.-3% Cal.Cl.
& 3 sacks of hulls. Pumped into 5 1/2" casing w/pump truck 2 sacks hulls & 175
sacks cement. Pumped into 8 5/8" S.P. 1 sack hulls & 75 sacks cement.

Maximum Pressure 500 pounds.

Amount of Surface Casing: 243' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed:
Conservation Division Agent

INVOICED
DATE 5-7-82
INV. NO. 124-u

RWD
05-07-82