

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- - (over) ←

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Liberty Enterprises, Inc.

Complete Address 308 W. Mill, Planville, Ks. 67663

Lease Name Mariana Well No. 1

Location SE SW NE Sec. 16 Twp. 11 Rge. 17 (East) (West)

County Ellis Total Depth 3414'

Abandoned Oil Well XXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Ks. 67524 License No.

Operation Completed: Hour: 4:30 PM Day: 22 Month: Jan Year: 19 82

Plugging Operations attended by Agent?: AllXXX Part None

The above well was plugged as follows:

8 5/8" 1050' S.P. cuc. W/ common cement. 4 1/2" casing set at 3398' W/ 150 sacks
common cement. Plugged back to 3386'. Top perf. 3092'. Pushed plug to 3000' W/
sand and 4 sacks cement on top. Shot pipe 1 time, recoverd 2650'. Ordered 140
sacks 50/50 posmix 4% Gel.-3% Cal.Cl., 5 sacks hulls, 19 sacks Gel. and 8 5/8"
plug. Pumped into 8 5/8" S.B. with pump truck; 4 sacks hulls, 15 sacks Gel., 70
sacks cement, 4sacks Gel., 1 sack hulls, released 8 5/8" plug and followed with
70 sacks cement. Maximum Pressure 700 pounds.

Amount of Surface Casing: 1050' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

Signed:
Conservation Division Agent

JAN 25 1982
26 82
9/18/82
Wichita, Kansas