

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 50-3  
LOCATION SW SW SE  
SEC. 16 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. A-5 Lease Remis "A"

Operator Sohio <sup>Petr. Co</sup> Oil Co Address Box 675 Russell, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3362 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

15" at 150' circulated with cement - 10 3/4" at 1047' circulated

with 3/5 sax cement - 7" 3541' with 125 sax cement behind -

Sand to 3320', set 5 sax cement with dump bailer, pulled 2300'

7" to 1000', circulated hole with heavy mud ( 45 sax Gel ) through

7" - heavy mud to 550', displaced 25 sax cement through 7" at 550',

heavy mud to 200', set cementing plug and displaced 20 sax cement

through 7", heavy mud to 30', set rock and 10 sax cement to bottom

cellar.

*Edward Letty*  
District Conservation Agent

10-18-57

Date \_\_\_\_\_

RECEIVED  
OCT 21 1957  
DIVISION

10-21-57

PLUGGING  
FILE SEC. 16 T. 11 R. 17W  
BOOK PAGE 50 LINE 3