

KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

R

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 145-23 Location: SE SW SE
County: Ellis Sec. 16 Twp. 11 Rge. 17 (E) (W)
Name of Field or Pool: _____ Total Depth: 3329

I have this date completed supervision of plugging of:

Well No. 4 Lease Bemis
Operator's Full Name Petroleum
Sohio Oil Co ANB KCC
Complete Address: Box 673 Russell, Kans
Plugging Contractor: West Supply Co
Address: Chase, Kans License No. 14
Abandoned Oil Well Gas Well Input Well SWD Well D & A
If well is a rotary drilled dry hole did operators wait for you to arrive _____
If yes how long _____ Reason: _____

Operation Completed: Hour 4PM Day 10 Month 12 Year 58

The above well was plugged as follows:

10 3/4" ar 1040' circulated with cement - 7" 3227' with 125 sax
cement behind - P.B. to 3050', perforated 2934'.
Filled with sand to 2920', set 5 sax cement with dump bailer, pulled
2540', 7" to 500', circulated hole with heavy mud through 7" at 500',
displaced 20 sax cement through 7" at 500', heavy mud to 150', displaced
20 sax cement through 7" at 150', heavy mud to 35', set rock and 10
sax cement to bottom cellar.

Mudding and cementing by West Supply Co's pump truck.
I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: *Jewel M. Ogden*
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1958

CONSERVATION DIVISION
Wichita, Kansas

Reviewed: *J. Lewis Bush*
Field Supervisor

Signed: _____
Well Plugging Supervisor

Remarks:

PLUGGING
FILE SEC 16 T. 11 R. 17W
BOOK PAGE 145 LINE 23