

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 1 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Sohio Petroleum Company

Complete Address Box 673 Russell, Kansas 67665

Lease Name Bemis "A" Well No. 3

Location SW SE SE Sec. 16 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3333'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11:30 A Day 29 Month 6 Year 1974

The above well was plugged as follows:

Total Depth 3333' 15 1/2" csg 114' cwc: 10" csg 1026' cwc

7" csg 3328' cw 250 sk cmt. & perf. (2929'-2939')

Set 7" wood plug at 2950' -poured sand (2950-2900) dumped 6 sk cmt W/dump bailer.

Cutoff and recovered 2270' of 7" csg.

Filled 10 3/4 csg with mud to 325' -set rock & sand bridge (325-310)

Filled with readymix cement from 310' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 7/2/74

INV. NO. 9443-W