

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

Received
07-01-82

API Number 15-167-21320-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Petro-Lewis Corporation

Complete Address 3100 N. Main, Great Bend, Ks. 67530

Lease Name *Steeber*
Stercker Well No. 1

Location SW SW NE Sec. 25 Twp. 13 Rge. 15 (East) (West)

County Ellis *Russell* Total Depth 3354'

Abandoned Oil Well XXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No.

Operation Completed: Hour: "2:45 PM Day: 24 Month: 6 Year: 19 82

Plugging Operations attended by Agent?: All XXXX Part None

The above well was plugged as follows:

8 5/8"-958' S.P. cuc. w/common cement. 5 1/2" set at 3354' w/100 sacks common
cement. Plug back T.D. 3340'. Top perf. 3322'. Plugged Bottom w/50' of sand
& 5 sacks cement. to 3260'. Shot pipe 5 times & recoverd 2320'. Ordered 140
sacks 50/50 posmix-4% Gel.-3% Cal.Cl., 15 sacks Gel., 4 sacks hulls, & 8 5/8"
plug. Pumped into 8 5/8" S.P. w/pump truck, 3 sacks hulls, 12 sacks Gel.,
70 sacks cement, 3 sacks Gel., 1 sacks hulls, released plug & followed w/70
sacks cement. Maximum pressure 600 pounds.

Amount of Surface Casing: 958' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: *[Signature]*
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

~~_____

_____~~

Signed: _____
Conservation Division Agent

INVOICED

DATE 7-1-82

INV. NO. 574-W