

DISTRICT CONSERVATION AGENT'S REPORT

[Handwritten signature/initials]

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION CS 1/2 NE NE

SEC. 25 TWP. 13 RGE. 15 W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease _____ Strecker 316 Brown Bldg.

Operator Bishop Oil Co Address Wichita, Kans

Field _____ County Russell

Total Depth 3398 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 181' circulated with cement. 5 1/2" at 3396' with 100
sax cement behind. Lane Wells plugs to 3100', top perf at 3086',
Filled with chat to 3080', set 4 sax cement with dump bailer,
pulled 3685' 5 1/2", filled hole with mud to 180', set rock bridge
and 15 sax cement, filled with heavy mud to 35', set rock bridge
and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1951
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent

Date 3-8-51

PLUGGING
FILE SEC 25 T 13 R 15 W
BOOK PAGE 66 LINE 39