

15-167-05382-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 149-5LOCATION NW-NW-NWSEC. 25 TWP. 13 RGE. 15W.Dry Hole _____ Abandoned Oil Well ☒ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Strucker
Operator Earl Habefield Address 306-7 Union Nat'l Bank Bldg. Wichita, Kans.
Field _____ County Russell

Total Depth 3374' Feet.Plugging Contractor Earl Habefield

Plugging Contractor's License No. _____

Address 306-7 Union Nat'l Bank Bldg. Wichita, Kans.
(Describe briefly the manner in which the well was plugged)

Surface pipe 10" @ 945' c.w.c. 850 sq. 5 1/2" set @
3329' c.w.c. 75 sq. Sand back to 3314' & 5 sq. cm.
Ripped 5 1/2" off @ 2910' & pulled same. Filled hole
w/ heavy mud to 300' from top, set plug & rock
bridge & 20 sq. cm. w/ dump bails. Then mud
to 35' from top, set plug & rock bridge & 10 sq.
cm. to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1955
CONSERVATION DIVISION
Wichita, Kansas

Milton Schaub
District Conservation Agent

DATE 9-19-55

PLUGGING
FILE SEC 25 T 13 R 15W
BOOK PAGE 149 LINE 5