

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock

Administrator
245 North Water

Wichita, KS 67202

API Number 15 - 077 - 20508-0000 (of this well)

Operator's Full Name W. L. Kirkman Inc.

Complete Address 453 S. Webb Rd., Box 18611, Wichita, Ks. 67207

Lease Name Kastens Well No. 1

Location C SE SW Sec. 27 Twp. 33s Rge. 8 (E) (W) X

County Harper Total Depth 4662

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling.


Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 1 Pm. Day 4 Month 9 Year 1980

The above well was plugged as follows:

295' 8 5/8" casing w/200 sax cement. 4 1/2" casing set at 4648' w/200
sax cement. Sand back to 4600'-Top sand w/4 sax mixed cement w/dump
bailer-Pull 3580' casing-Sun mixed & pumped 8 sax hulls-20 sax gel-
100 sax 50/50 posmix cement w/4% gel & 3% cc in 8 5/8" casing to 0.
Shut in w/250# pressure.

I hereby certify that the above well was plugged as herein stated.

Signed: 
Well-Plugging Supervisor, CONSERVATION COMMISSION

INVOICED

DATE 9-12-80

INV. NO. 3092w

SEP - 8 1980
09-08-80
CONSERVATION DIVISION
Wichita, Kansas