

CONFIDENTIAL

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1  
September 1999  
Form Must Be Typed

WELL COMPLETION FORM  
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 4767  
Name: Ritchie Exploration, Inc.  
Address: P.O. Box 783188  
City/State/Zip: Wichita, KS 67278-3188  
Purchaser: \_\_\_\_\_  
Operator Contact Person: John Niernberger  
Phone: (316) 691-9500  
Contractor: Name: BEREDCO, Inc.  
License: 5147  
Wellsite Geologist: Steve Carl

Designate Type of Completion:  
 New Well     Re-Entry     Workover  
 Oil     SWD     SLOW     Temp. Abd.  
 Gas     ENHR     SIGW  
 Dry     Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Original Comp. Date: \_\_\_\_\_ Original Total Depth: \_\_\_\_\_  
 Deepening     Re-perf.     Conv. to Enhr./SWD  
 Plug Back     Plug Back Total Depth  
 Commingled    Docket No. \_\_\_\_\_  
 Dual Completion    Docket No. \_\_\_\_\_  
 Other (SWD or Enhr.?)    Docket No. \_\_\_\_\_

7/13/08	7/24/08	7/26/08
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 057-20611-0000  
County: Ford  
approx. SE NW NW Sec. 4 Twp. 28 S. R. 22  East  West  
1026 feet from S / N (circle one) Line of Section  
1197 feet from E / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE SE NW SW  
Lease Name: Stephenson 4B Well #: 1

Field Name: \_\_\_\_\_  
Producing Formation: \_\_\_\_\_  
Elevation: Ground: 2366 Kelly Bushing: 2375  
Total Depth: 5185 Plug Back Total Depth: 5165  
Amount of Surface Pipe Set and Cemented at 336 Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set 1412 Feet  
If Alternate II completion, cement circulated from 1412  
feet depth to surface w/ 335 sx cmt.

Drilling Fluid Management Plan 1-11-11-NH 1-7-09  
(Data must be collected from the Reserve Pit)  
Chloride content 15500 ppm Fluid volume 1800 bbls  
Dewatering method used evaporation  
Location of fluid disposal if hauled offsite: \_\_\_\_\_  
Operator Name: \_\_\_\_\_  
Lease Name: \_\_\_\_\_ License No.: \_\_\_\_\_  
Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  East  West  
County: \_\_\_\_\_ Docket No.: \_\_\_\_\_

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]  
Title: Production Manager Date: 10/29/08  
Subscribed and sworn to before me this 29<sup>th</sup> day of October,  
20 08.  
Notary Public: [Signature]  
Date Commission Expires: 5-4-11

DEBRA K. PHILLIPS  
Notary Public - State of Kansas  
My Appt. Expires 5-4-11

**KCC Office Use ONLY**

Letter of Confidentiality Received  
If Denied, Yes  Date: \_\_\_\_\_  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
**OCT 30 2008**

CONSERVATION DIVISION  
WICHITA, KS

Operator Name: Ritchie Exploration, Inc. Lease Name: Stephenson 4B Well #: 1  
 Sec. 4 Twp. 28 S. R. 22  East  West County: Ford

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Attach Additional Sheets)</i>  Samples Sent to Geological Survey <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i>  List All E. Logs Run:  <b>Dual Induction Log</b> <b>Compensated Density/Neutron Log</b>	<input type="checkbox"/> Log Formation (Top), Depth and Datum <input checked="" type="checkbox"/> Sample Name Top Datum  <p style="text-align: center; font-size: 1.2em;">SEE ATTACHED</p> <p style="text-align: center; font-size: 1.5em; font-weight: bold;">KCC</p> <p style="text-align: center; font-size: 1.2em;">OCT 29 2008</p> <p style="text-align: center; font-size: 1.2em; font-weight: bold;">CONFIDENTIAL</p>
---	---

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4	8-5/8	23	336	class A	300	3%cc, 2% gel
Production	7-7/8	4-1/2	10.5	5167	ASC	200	10% salt, 1% gel, Kol-sel

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
	***No Perforation Records yet waiting on gas market***		

TUBING RECORD	Size	Set At	Packer At	Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr.		Producing Method <input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio Gravity

Disposition of Gas <input type="checkbox"/> Vented <input type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	METHOD OF COMPLETION <input type="checkbox"/> Open Hole <input type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. <input type="checkbox"/> Commingled <input type="checkbox"/> Other (Specify) _____	Production Interval _____
---	---	---------------------------

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 30 2008

CONSERVATION DIVISION  
WICHITA, KS



**#1 Stephenson 4B**

1026' FNL & 1197' FWL

36' S & 207' E of SE NW NW Section 4-28S-22W

Ford County, Kansas

API# 15-057-20611-00-00

Elevation: 2366' GL, 2375' KB

<u>Sample Tops</u>			<u>Ref.</u> <u>Well</u>
B/Anhydrite	1412'	+963	-13
Chase Herrington	2564'	-189	-10
Stotler	3480'	-1105	-2
Heebner	4142'	-1767	-8
Lansing	4280'	-1905	-6
Stark Shale	4602'	-2227	-6
Pawnee	4809'	-2434	-5
Cherokee Shale	4857'	-2482	-8
Atoka Shale	4945'	-2570	-5
Miss. Spergen	4962'	-2587	flat
RTD	5185'	-2810	

KCC  
OCT 29 2008  
CONFIDENTIAL

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 30 2008

CONSERVATION DIVISION  
WICHITA, KS

# ALLIED CEMENTING CO., LLC. 31268

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Medicine Lodge

DATE <u>2-31-08</u>	SEC <u>4</u>	TWP <u>28 S</u>	RANGE <u>22 W</u>	CALLED OUT <u>1:30 pm</u>	ON LOCATION <u>2:00 pm</u>	JOB START <u>3:40 pm</u>	JOB FINISH <u>5:30 pm</u>
LEASE <u>416</u>	WELL # <u>1</u>	LOCATION <u>FORD, KS, POST OFFICE</u>			COUNTY <u>FORD</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>OLD</u>				<u>1/4 EAST, N INTO</u>			

CONTRACTOR PLAINS OWNER RITCHIE EXPLORATION

TYPE OF JOB PORT COLLAR  
 HOLE SIZE 7 7/8" T.D. 1,412'  
 CEMENTING AMOUNT ORDERED 475 SK 60:40:6% CO<sub>2</sub>  
+ 1/4" FLO-SEAL, (USED 330 SK)

TUBING SIZE 2 3/8" DEPTH 1,412'  
 DRILL PIPE DEPTH  
 TOOL DEPTH  
 PRES. MAX 1,200 MINIMUM 100  
 MEAS. LINE SHOE JOINT  
 CEMENT LEFT IN CSG.

PERFS.  
 DISPLACEMENT 4 1/2 bbl. FRESH WATER  
 EQUIPMENT

PUMP TRUCK CEMENTER BILL M.  
 # 352 HELPER MIKE B.  
 BULK TRUCK  
 # 363 DRIVER NEWTON D.  
 BULK TRUCK  
 # DRIVER

COMMON 198 A @ 15.45 3059.10  
 POZMIX 132 @ 8.00 1056.00  
 GEL 17 @ 20.80 353.60  
 CHLORIDE @  
 ASC @  
 FLO SEAL 83 @ 2.50 207.50  
 @  
 @  
 @  
 @  
 @  
 HANDLING 505 @ 2.40 1212.00  
 MILEAGE 50 X 505 X .10 2525.00  
 TOTAL 8413.20

REMARKS:  
PORT COLLAR @ 1,412', TEST PORT COLLAR  
TO 1,200', OK, OPEN PORT COLLAR, EST.  
CIRCULATION, PUMP 330 SK 60:40:6% CO<sub>2</sub>  
+ 1/4" FLO-SEAL, 6 BBL @ 900-500-700'  
CIRCULATE CEMENT TO SURFACE, STOP PUMPS  
WASH PUMP + LINES, START DISPLACEMENT,  
1/2 BBL @ 200', STOP LIFT, 400', DISPLACE  
4 1/2 bbl. FRESH WATER, STOP PUMP, CLOSE  
PORT COLLAR, PRESSURE TEST TO 1,200',  
OK, RUN IN 5 JTS, REVERSE OUT, OK,

CHARGE TO: RITCHIE EXPLORATION  
 STREET  
 CITY STATE ZIP

TOTAL 1535.00

PLUG & FLOAT EQUIPMENT  
 @  
 @  
 @  
 @  
 @  
 TOTAL

SALES TAX (If Any)  
 TOTAL CHARGES 8413.20  
 DISCOUNT 0 IF PAID IN 30 DAYS

ANY APPLICABLE TAX  
 WILL BE CHARGED  
 UPON INVOICING

PRINTED NAME GARY ROWE  
 SIGNATURE Gary Rowe

KCC  
 OCT 29 2008  
 CONFIDENTIAL

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 WICHITA, KS  
 OCT 30 2008

72-

# ALLIED CEMENTING CO., LLC. 31256

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
*MEDICINE LODGE*

*10/30/08*

DATE <i>7-13-08</i>	SEC <i>4</i>	TWP <i>28S</i>	RANGE <i>22W</i>	CALLED OUT <i>10:30 am</i>	ON LOCATION <i>2:30 pm</i>	JOB START <i>3:30 pm</i>	JOB FINISH <i>4:00 pm</i>
STEPHENSON LEASE		WELL # <i>45</i>	LOCATION <i>FORD, KS EAST OFFICE, 1/2 EAST,</i>		COUNTY <i>FORD</i>	STATE <i>KS</i>	
OLD OR NEW (Circle one)			<i>1/2 SOUTH NORTH</i>				

CONTRACTOR *BELVED CO* OWNER *RITCHIE EXPLORATION*

TYPE OF JOB *SURFACE CASING*  
 HOLE SIZE *12 1/4"* T.D. *337'*  
 CASING SIZE *8 5/8"* DEPTH *336'*  
 TUBING SIZE DEPTH  
 DRILL PIPE *4 1/2"* DEPTH  
 TOOL DEPTH

CEMENT  
 AMOUNT ORDERED *300 SX CLASS AT 390 CC*  
*128 GGL*

PRES. MAX *300* MINIMUM *100*  
 MEAS. LINE SHOE JOINT *15'*  
 CEMENT LEFT IN CSG. *15'*  
 PERFS.  
 DISPLACEMENT *20 1/4 GGL FRESH WATER*

COMMON	<i>300 A</i>	@	<i>15.45</i>	<i>4635.00</i>
POZMIX		@		
GEL	<i>6</i>	@	<i>20.80</i>	<i>124.80</i>
CHLORIDE	<i>11</i>	@	<i>58.20</i>	<i>640.20</i>
ASC		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<i>317</i>	@	<i>2.40</i>	<i>760.80</i>
MILEAGE	<i>50 X 317 X .10</i>			<i>1585.00</i>
				TOTAL <i>7745.80</i>

EQUIPMENT

PUMP TRUCK CEMENTER *BILL M.*  
 # *360* HELPER *RAYMOND R.*  
 BULK TRUCK  
 # *368* DRIVER *RICK M.*  
 BULK TRUCK  
 # DRIVER

REMARKS:

*PIPE ON BOTTOM, BREAK CIRCULATION,  
 PUMP PRE-FRESH, PUMP 300 SX CLASS AT  
 390 CC + 28 GGL, STOP PUMPS, RELEASE  
 PLUG, START DISPLACEMENT, SOB LINE,  
 SLOW RATE, DISPLACE WITH 20 1/4 GGL  
 FRESH WATER, STOP PUMPS, SOB LINE,  
 CIRCULATE CEMENT.*

SERVICE

DEPTH OF JOB	<i>336'</i>		
PUMP TRUCK CHARGE	<i>0-300'</i>		<i>1018.00</i>
EXTRA FOOTAGE	<i>36'</i>	@	<i>.85</i> <i>30.60</i>
MILEAGE	<i>50</i>	@	<i>7.00</i> <i>350.00</i>
MANIFOLD	<i>HEAD ROENT</i>	@	<i>113.00</i> <i>113.00</i>
		@	
		@	

CHARGE TO: *RITCHIE EXPLORATION*  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

TOTAL *1511.60*

PLUG & FLOAT EQUIPMENT

<i>8 1/2" RUBBER PLUG</i>	<i>1</i>	@	<i>113.00</i>	<i>113.00</i>
		@		
		@		
		@		
		@		
				TOTAL <i>113.00</i>

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (If Any) \_\_\_\_\_  
 TOTAL CHARGES *1624.60*  
 PRINTED NAME *Marvin B. Julian* DISCOUNT ~~\_\_\_\_\_~~ IF PAID IN 30 DAYS

SIGNATURE *Marvin B. Julian*

ANY APPLICABLE TAX  
 WILL BE CHARGED  
 UPON INVOICING

KCC  
 OCT 29 2008  
 CONFIDENTIAL

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 WICHITA, KS  
 OCT 30 2008

# ALLIED CEMENTING CO., LLC. 34223

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
*Medicine Lodge, KS.*

DATE <i>7-25-08</i>	SEC. <i>4</i>	TWP. <i>24S</i>	RANGE <i>22W</i>	CALLED OUT <i>5:00 AM</i>	ON LOCATION <i>6:00 PM</i>	JOB START <i>3:00 PM</i>	JOB FINISH <i>5:00 PM</i>
LEASE <i>Stephenson 4B</i>		WELL # <i>1</i>	LOCATION <i>Ford, KS, 1E, 1/2N, W I-70</i>		COUNTY <i>Ford</i>	STATE <i>KS</i>	
OLD OR NEW (Circle one)							

CONTRACTOR *Boredco*  
 TYPE OF JOB *Production casing*  
 HOLE SIZE *7 7/8* T.D. *5181'*  
 CASING SIZE *4 1/2* 10.5 DEPTH *5181'*  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX *3,000* MINIMUM *1000*  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT *43*  
 CEMENT LEFT IN CSG. *0.7*  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_

OWNER *Ritchie Exploration*

CEMENT  
 AMOUNT ORDERED *225 SK ASC + 5 # Kol Seal*  
*SK + 5% FL-160, 500 GAL ASF*

EQUIPMENT

PUMP TRUCK # <i>360</i>	CEMENTER <i>Thomas Demorrow</i>
BULK TRUCK # <i>381</i>	HELPER <i>Greg K.</i>
BULK TRUCK # _____	DRIVER <i>Jasank</i>
BULK TRUCK # _____	DRIVER _____

COMMON	@		
POZMIX	@		
GEL	@		
CHLORIDE	@		
ASC <i>225</i>	@	<i>18.60</i>	<i>4185.00</i>
<i>Kol Seal 1125#</i>	@	<i>.89</i>	<i>1001.25</i>
<i>FL-160 106#</i>	@	<i>13.30</i>	<i>1409.80</i>
<i>ASF 500 gal.</i>	@	<i>1.27</i>	<i>635.00</i>
HANDLING <i>289</i>	@	<i>2.40</i>	<i>693.60</i>
MILEAGE <i>50 x 289 x .10</i>			<i>1445.00</i>
TOTAL			<i>9369.65</i>

REMARKS:

*Pipe on bottom Break circulating Pump  
 Pre flush - 386L Fresh, 500GAL ASF, 386L  
 Fresh, 1/2 gal Rot + mouse w/ 25 SK ASC + 5 #  
 Kol Seal SK + 5% FL-160, Pump Production 200  
 SK ASC + 5 # Kol Seal SK + 5% FL-160, well  
 locked up Pressured up to 3,000# and  
 not get it to Break loose, Decided to pull  
 pipe & trip in to recondition hole*

CHARGE TO: *Ritchie Exploration*  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

SERVICE

DEPTH OF JOB <i>5181'</i>		
PUMP TRUCK CHARGE		<i>2295.00</i>
EXTRA FOOTAGE	@	
MILEAGE <i>50</i>	@	<i>7.00</i>
MANIFOLD	@	
<i>Head Rental</i>	@	<i>113.00</i>
TOTAL <i>2758.00</i>		

PLUG & FLOAT EQUIPMENT

<i>Guide Shoe</i>	1 @	<i>169.00</i>	<i>169.00</i>
<i>Arc Insert</i>	1 @	<i>254.00</i>	<i>254.00</i>
<i>Foot collar</i>	1 @	<i>1800.00</i>	<i>1800.00</i>
<i>Baskets</i>	2 @	<i>169.00</i>	<i>338.00</i>
<i>Turbolizers</i>	6 @	<i>68.00</i>	<i>408.00</i>
TOTAL			<i>2969.00</i>

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME *X John Newberry*  
 SIGNATURE *X [Signature]*

SALES TAX (If Any) \_\_\_\_\_  
 TOTAL CHARGES ~~9369.65~~  
 DISCOUNT ~~9369.65~~ IF PAID IN 30 DAYS  
**ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING**

KCC  
 OCT 29 2008  
 CONFIDENTIAL

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 OCT 30 2008  
 CONSERVATION DIVISION  
 WICHITA, KS

# ALLIED CEMENTING CO., LLC. 32331

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Madras

DATE <u>7-26-08</u>	SEC <u>4</u>	TWP <u>28</u>	RANGE <u>22W</u>	CALLED OUT	ON LOCATION	JOB START <u>12:00pm</u>	JOB FINISH <u>1:00pm</u>
STEVENSON LEASE	WELL # <u>4R #1</u>	LOCATION <u>Ford Rs Post office</u>		COUNTY <u>Ford</u>	STATE <u>Ks</u>		
OLD OR NEW (Circle one) <u>NEW</u>		<u>2 E units</u>					

CONTRACTOR Beredas OWNER Ritchie Exp

TYPE OF JOB Pipe/CSG  
 HOLE SIZE 7 7/8 T.D. 5185  
 CASING SIZE 4 1/2 DEPTH 5184  
 TUBING SIZE DEPTH  
 DRILL PIPE DEPTH  
 TOOL DEPTH  
 PRES. MAX MINIMUM  
 MEAS. LINE SHOE JOINT 21  
 CEMENT LEFT IN CSG. 21 ft  
 PERFS.

CEMENT  
 AMOUNT ORDERED 200 of Asc 5# Kolseal  
.52 lb-160 + 500 gal ASF

DISPLACEMENT 82 1/2 bbls fresh water  
 EQUIPMENT

COMMON	@		
POZMIX	@		
GEL	@		
CHLORIDE	@		
ASC 200	@	18.60	3720.00
Kol Seal 1000 #	@	1.89	890.00
FK-160 94 #	@	13.30	1250.20
ASF 500 gal.	@	1.27	635.00
	@		
	@		
	@		
	@		
HANDLING	@	2.57	616.80
MILEAGE		50 x 2.57 x .10	1285.00
		TOTAL	8397.00

PUMP TRUCK CEMENTER Mark B  
 # 372 HELPER Heath  
 BULK TRUCK  
 # 381 DRIVER Greg J  
 BULK TRUCK  
 # DRIVER

REMARKS:  
Pipe on bottom + circulate pump 3 bbls  
fresh, 500 gal mud flush 3 bbls fresh  
mix 200 of Asc 5 # Kolseal + .52 lb-160  
shut down pump, wash pump + line  
+ release plug, start displacement  
left pressure at 60 bbls + stop  
late to 3 bbls bump plug at  
82 1/2 bbls + 500 gal float discharge

CHARGE TO: Ritchie Exp  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

SERVICE  
 DEPTH OF JOB 5184'  
 PUMP TRUCK CHARGE 2295.00  
 EXTRA FOOTAGE @ \_\_\_\_\_  
 MILEAGE 50 @ 7.00 350.00  
 MANIFOLD @ \_\_\_\_\_  
head rental @ 113.00 113.00  
 @ \_\_\_\_\_  
 TOTAL 2758.00

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PLUG & FLOAT EQUIPMENT  
4 1/2  
 1- Guide shoe @ 169.00 169.00  
 1- API cement @ 254.00 254.00  
 6- Tailpiece @ 68.00 408.00  
 2- Backbit @ 169.00 338.00  
 1- Post collar @ 1800.00 1800.00  
 1- plug TR @ 62.00 62.00  
 TOTAL 3031.00

PRINTED NAME John N. Stevenson  
 SIGNATURE [Signature]

SALES TAX (If Any) \_\_\_\_\_  
 TOTAL CHARGES [scribble]  
 DISCOUNT [scribble] IF PAID IN 30 DAYS

ANY APPLICABLE TAX  
 WILL BE CHARGED  
 UPON INVOICING

KCC  
 OCT 29 2008  
 CONFIDENTIAL

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 WICHITA, KS  
 OCT 30 2008